# Structures Inspection Workbook

Certified Inspector Training Program



#### **TABLE OF CONTENTS**

- Introduction
- Standard Specs
- Construction Manual
- CIT Documentation
- Bridge Construction Manual
- Project Plan Sheets
- Concrete and Reinforcing Steel
- Foundations
- Pile Driving
- Forms and Falsework
- Substructure
- Superstructures
- Decks
- Curing
- Concrete Review
- Forms and Falsework Review
- Pile Driving Review



**CIT Structures Introduction** 

1

# **CIT Structures Instructors**

- Ian Stringham Garnett Construction Manager
- Cooper Bettis Bridge Designer
- Ben Dyhouse Bridge Designer



## **Contact Information:**

· Ian Stringham:

913-406-1986 Ian.Stringham@ks.gov

Cooper Bettis:

785-269-5006 Cooper.Bettis@ks.gov

Ben Dyhouse:

785-296-6469 Ben.Dyhouse@ks.gov



3

# What this class is and is not

- This **is** an introductory class dealing with some of the important aspects of inspecting structures.
- This <u>is</u> a class to help clue you into where to find the information to do your job successfully.
- This **is not** going to tell you everything you need to know to be a good inspector. That takes time and experience.



# Keys to being successful

- Relax and remember you can pass this class.
- Ask questions.
- Don't memorize the details/specs, they change too often. Learn how and where to find the details; Standard specifications, plans, special provisions, project specific special provisions.
- Be respectful to others.
- Enjoy yourself.



# **CIT – Structures Standard Specifications**

SS--1

1

- What are they?
- Who are they for?
  - KDOT
  - The Contractor
  - Local Projects
  - Outside entities (FHWA, DWR, AASHTO)



#### 1. Project Special Provisions:

- · Specifications pertaining to an individual Project;
- 2. 2015 Special Provisions:
  - Revisions or Additions to the Standard Spec.;
- 3. Plan Notes:
  - Notes setting work limits and specifying Bid Items:
  - 4. 2015 Standard Specifications:
    - Overall standing parameters by which all works are constructed and paid for.



3

- Division 150 Equipment
- Division 200 Earthwork
- Division 400 Concrete
- Division 700 Structures



# 1. Project Special Provisions

# -Example

(PS Label)

10-23 KA-1826-01

#### KANSAS DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION TO THE STANDARD SPECIFICATIONS, 2007 EDITION

OSTERBERG CELL LOAD TEST (DRILLED SHAFT)

Conduct Osterberg Cell (O-Cell) load tests at the locations designated in the Contract Documents

BID ITEM
Osterberg Cell Load Test (Drilled Shaft)

2.0 MATERIALS

2.0 MATERIALS
Provide O-Cells with the minimum capacity (in each direction) designated in the Contract Documents. Provide O-Cells equipped with the necessary hydraulic lines, fittings, pressure sources, pressure gages, and telltale devices. Provide O-Cells from either:

1.0.ADTEST, Inc.
1.0.ADTEST, Inc.
2631-D NW 41st Street
1.0.ADTEST, Inc.
2631-D NW 41st Street
1.0.ADTEST, Inc.
2631-D NW 21584
2.0.CELL MILE RA, Suite 4
3.0.CELL Telephone: (800) 368-1138 Telephone: (800) 436-2355 or (352) 378-3717 Fax: (352) 378-3934 or (410) 552-1979 Fax: (410) 552-1843

The Engineer will accept the O-Cell based on brand name, compliance with the specified requirements, and

visual inspection for condition at the point of usage.

Provide a recognized brand of portland cement and water from a source approved by the Engineer for the grout. The Engineer will accept the portland cement and water based on visual inspection.



5

# 2015 Special Provisions

2015 SPECIAL PROVISION

<u>List All Special Provisions</u> <u>Latest Version of Special Provisions</u> <u>Help</u>

Special Provision Divisions:

100 - General Clauses and Convents

600 - Flexible Pavement

150 - Equipment

700 - Structures

200 - Earthwork

 $\underline{300}$  - Stabilized Subgrade, Base and Shoulders  $\underline{900}$  - Roadside Improvement, Planting, and Seeding

400 - Concrete

1000 - Materials

500 - Rigid Pavement

Questions or Comments about Special Provisions may be sent to:

Construction - Lee Ann Legge Materials - Stacey Lowe

ALL LATEST 100 150 200 300 400 500 600 700 800 900 MATERIALS HELP



# 2. 2015 Special Provisions

#### 200- Earthwork

2015 SPECIAL PROVISION

rev. 12/01/15

ALL LATEST 100 150 200 300 400 500 600 700 800 900 MATERIALS HELP

SECTION 200

SPECIFICATION NUMBER TITLE SECTION 15-02001 REMOVAL OF EXISTING STRUCTURES 202

400- Concrete

rev. 6/17/15

SECTION

2015 SPECIAL PROVISION

ALL LATEST 100 150 200 300 400 500 600 700 800 900 MATERIALS HELP

SECTION 400

SPECIFICATION NUMBER TITLE

15-04001 KANSAS CITY METRO MATERIALS



7

# 2. 2015 Special Provisions

#### 700- Structures

2015 SPECIAL PROVISION

SPECIFICATION NUMBER

ALL LATEST 100 150 200 300 400 500 600 700 800 900 MATERIALS HELP


SECTION 700

BRIDGE PROJECT MARKER
PRESTRESSED CONCRETE MEMBERS
STRUCTURAL STEEL FABRICATION
STRUCTURAL STEEL FABRICATION
STRUCTURAL STEEL FABRICATION
STRUCTURAL STEEL FABRICATION
STRUCTURAL METALS FABRICATION
STRUCTURAL METALS FABRICATION
OUALIFICATION OF FIELD WELDERS
EXPANSION JOINTS
DRILLED SHAFT (SPECIAL)
SIGN STRUCTURES AND BRIDGE MOUNTED SIGN ATTACHMENTS
HIGH MAST LIGHT TOWERS

rev. 09/28/16

SECTION









# 4. 2015 Standard Specification

Typical information provided in each Section:

- Description (for Bid Items & Units)
- Materials
- Construction Requirements
- Measurement & Payment



12

# 4. 2015 Standard Specifications

# 150- Equipment

#### **DIVISION 150 - EQUIPMENT**

<u>151</u>	COMPACTION EQUIPMENT
152	HAULING AND WEIGHING EQUIPMENT
<u>153</u>	MIXING PLANT FOR STABILIZED BASE AND SHOULDERS
154	CONCRETE PAVEMENT AND CONCRETE STRUCTURE EQUIPMENT
155	ASPHALT SURFACING AND ASPHALT PAVEMENT RECYCLING EQUIPMENT
	15-ER-1-R08 - ERRATA SHEET FOR STANDARD SPECIFICATION BOOK FOR STATE ROAD AND BRIDGE
	CONSTRUCTION, EDITION 2015
<u>156</u>	ROADSIDE IMPROVEMENT EQUIPMENT
157	OTHER EQUIPMENT



13

# 4. 2015 Standard Specifications

## 200- Earthwork

#### **DIVISION 200** - EARTHWORK

201	CLEARING AND GRUBBING
201 202	REMOVAL OF EXISTING STRUCTURES
	15-02001 - REMOVAL OF EXISTING STRUCTURES
203	RESETTING EXISTING CULVERTS
204	EXCAVATION AND BACKFILL FOR STRUCTURES
205	EXCAVATION AND EMBANKMENT FOR HIGHWAYS
206	SELECT SOIL
207	OVERHAUL
203 204 205 206 207 208	LINEAR GRADING
209	SPECIAL FILL
209 210	SALVAGING, STOCKPILING AND PLACING TOPSOIL
211	GEOFOAM LIGHTWEIGHT EMBANKMENT FILL
212	GEOFOAM LIGHTWEIGHT EMBANKMENT FOR VOID FILL
213	PREFABRICATED VERTICAL DRAIN
212 213 214	MECHANICALLY STABILIZED EARTH FILL
215	GRANULAR DRAINAGE BLANKET



# 4. 2015 Standard Specifications

#### 400- Concrete

**DIVISION 400 - CONCRETE** 

 401
 GENERAL CONCRETE

 402
 STRUCTURAL CONCRETE

 403
 ON GRADE CONCRETE

 404
 CONCRETE FOR PRESTRESSED CONCRETE MEMBERS

 405
 CURING ENVIRONMENT

15-04001 - KANSAS CITY METRO MATERIALS Return to Top



15

DOMAIN ROLLED SAUTH

THE PORANT STORING

TO CHARLES AND THE PORANT STORING

TO CHARLES

# 4. 2015 Standard Specification

Example- 703 Drilled Shafts:

Description -

703 - DRILLED SHAFTS

(Bid Items/Units)

SECTION 703

DRILLED SHAFTS

Construct drilled shafts by the cased or uncased method deper Document requirements.

> BID ITEMS UNITS Drilled Shaft (\*) (\*\*) Linear Foot Permanent Casing (\*) (Set Price) Linear Foot Sonic Test (Drilled Shaft) (Set Price) Each Core Hole (Investigative) Linear Foot

\*\*Cased (If Contract Documents specify the cased method.)





17

# 4. 2015 Standard Specification



# Example- 703 Drilled Shafts

#### - Materials

#### 703.2 MATERIALS

4. Concrete. Unless otherwise shown in the Contract Documents, provide Grade 4.0 concrete that complies with SECTIONS 401, 402 and 1102. Provide a mix design with a target slump of 9 inches ± 1 inch. Do not withhold mix water at the plant and do not add water at the site.

b. Grout/Flowable Fill. For backfilling the cross-hole sonic testing pipes and core holes, provide militious grout (mixed according to the manufacturer's directions) that complies with DIVTSION 1700. Provide grout or flowable fill for backfilling the void space between the temporary and permanent casing

- 28 day strength of 1000 psi;
   mortar sand, FA-M (SECTION 1102) mixed with 2 bags of Type II portland cement per cubic yard; and
   water-to-cement ratio less than 1.
- c. Granular Backfill Material. Provide granular backfill material for backfilling the void space between the temporary and permanent casing that is fine enough to fill the entire volume. The Engineer will accept the granular material based on a visual inspection.
  - d. Reinforcing Steel. Provide steel bars for concrete reinforcement that comply with DIVISION 1600

e. Casing. Provide casing of sufficient thickness to carry the working stresses and loads imposed on the casing during construction. At a minimum, use 14-gage corrugated metal pipe (CMP) for the permanent casing. If required, provide a permanent casing that is less than or equal to 1 inch out-of-round. The deviation of a chord from end to end shall be a maximum of 2 inches.

The Engineer will accept the casing based on compliance with the specified requirements, and visual inspection for condition.

f. Pipe for Sonic Testing. Provide pipe that complies with DIVISION 1900.





# Example- 703 Drilled Shafts

#### - Const. Requirements

703.3 CONSTRUCTION REQUIREMENTS

a. General. Drilled shaft lengths shown in the Contract Documents are an estimate from the top of formation elevations determined from borings. Actual formation elevations encountered at each shaft, may require the actual length of each drilled shaft be adjusted. If the Engineer changes the drilled shaft lengths, the Contractor will be advised (in writing) of the revised bottom of rock socket elevation.

A minimum of 28 days before constructing the drilled shafts, submit an installation plan to the Engineer for review. Include the following:

• Name and experience record of the drilled shaft superintendent in charge of drilled shaft operations;

- List of proposed equipment, such as cranes, drills, augers, bailing buckets, final cleaning equipment, desanding equipment, slurry pumps, core-sampling equipment, tremies or concrete pumps and casing; and
   Details of concrete placement, including proposed operational procedures for tremie and pumping methods and method of achieving a sealed tremie or pump.

b. Investigative Core Hole. Provide NX sized (2.125 inches) core samples organized in descending elevation and stored in standard core cardboard boxes. Perform this work, from the existing ground surface elevation, 15 working days in advance of the drilled shaft construction, at locations shown in the Contract Documents or ordered by the Engineer: Extract and maintain a core of the foundation material from 4 feet above the top of the plan tip elevation to 6 feet below the plan tip elevation shown in the Contract Documents. Discard all material extracted above 4 feet above the top of the plan tip elevation. Maintain, protect and label (elevation and location) these samples for review by the KDOT. While drilling, prepare a continuous standard drilling/coring log. The logs shall remain with the sample for review. Survey the location of the core hole with the same construction tolerance as subsection 703.3c.

c. Excavating the Drilled Shaft. Prior to constructing drilled shafts, complete the excavation for the entire

c. Excavating the Drilled Shaft. Prior to constructing drilled shafts, complete the excavation for the entire element.

Locate the top of the shaft within 2 inches of the location shown in the Contract Documents. Unless otherwise shown in the Contract Documents, bore all shafts plumb to within a tolerance of 1 inch per 10 feet of length of shaft, not to exceed 6 inches over the full length of the shaft. The bottom of the shaft shall be nearly flat. The cutting edges of excavation equipment shall be normal to the vertical axis of the equipment within a tolerance of

The cuting coges of excent and equipment stant or normal to the vertical axes or the equipment within a rotestance of ±9s inch per foot of diameter.

Depending upon site conditions and requirements in the Contract Documents, construct the drilled shaft by either the cased or uncased method:



19

#### 2015 S.S. Figures Concrete Brake (French Horn or Bladder Valve) (French Horn Shown) (Required to purge air.) METHOD 'A' (Figure 1) Underwater Placement of Pumped Concrete Flexible Hose Maintain head seal depth!! Inflatible Pig - Prime Pump Boom - Fully Charged System. - Lift and Develop Seal Maintain Seal - Uniform Removal Kansas Set on Bottom of Shaft \* Document whether or not the pig is recovered.

# 4. 2015 Standard Specification



# Example- 704 Piling Description -

(Bid Items/ Units)

#### 704.1 DESCRIPTION Drive the speci

UNITS
Linear Foot
Linear Foot
Linear Foot
Linear Foot
Each
Linear Foot
Each
Linear Foot
rete, Prestressed Concrete, Steel or Steel Sheet, Corrugated Metal Sheer' BID ITEMS Piles (\*) (\*\*)
Test Piles (\*) (\*\*)
Test Piles (Special) (\*) (\*\*)
Cast Steel Pile Points
Pre-Drilled Pile Holes
\*Type: Cast-In-Place Concrete,
\*\*Size \*Black or Galvanized



21

# 4. 2015 Standard Specification

Example- 704 Piling - Test Pile



#### 704.4 Construction Requirements

b. Test Pile (Special). Pile Driving Analyzer (PDA). The Engineer will use the PDA to monitor the driving of the test piles (special). Provide the Engineer with the completed "Pile and Driving Equipment Data" sheet a minimum of 3 weeks before the scheduled date of driving piling. The Engineer will forward this information to the Chief Geologist.

In order to mobilize the PDA, notify the Engineer a minimum of 5 working days before driving the test piles (special). Prior to driving the test pile (special), the Engineer will require approximately 1½ hours to prepare pines (special). From to diving the test pine (special), the Engineer will require approximately 193 nows to prepare the test piling (special) and install the dynamic measuring equipment. If with prior approval, the piles are to be welded prior to the Engineer attaching the testing equipment, provide the Engineer with safe and reasonable means of access to the pile for preparing the pile and attaching the instruments.

When a restrike is required by the Engineer, follow subsection 704.4e.(3), for restrike procedures.

To obtain the estimated ultimate loads, the Engineer will use the PDA to take dynamic measurements as the

test pile (special) is driven to the required driving resistance. If non-axial driving is indicated by dynamic test equipment measurements, immediately realign the driving system. The Engineer will use the PDA results to provide the Contractor with a blow count for production driving.



# 4. 2015 Standard Specification

TABLE 704-1: PILE FORMULAS						
Hammer	Pile Type	Formula				
Gravity	Timber	$P = \frac{2  W  H}{S + 1.0}$				
Gravity	Steel Steel Shell Steel Sheet	$P = \frac{3  W  H}{S + 0.35}  \left(\frac{W}{(W + X)}\right)$				
Air/Steam (Single Acting)	All Types	$P = \frac{2  W  H}{S + 0.1}$				
Air/Steam (Double Acting)	All Types	$P = \frac{2  E}{S + 0.1}$				
Delmag and McKierman-Terry*	All Types	$P = \frac{1.6  W  H}{S + 0.1  \left(\frac{X^{**}}{W}\right)}$				
Link-Belt*	All Types	$P = \frac{1.6 \text{ E}}{S + 0.1 \left(\frac{X^{**}}{W}\right)}$				

Example- 704 Piling

TABLE 704-1: PILE FORMULAS, (p. 700-19)

\*diesel hammers \*\* For diesel hammers, the quantity X/W shall not be less than 1.

P = safe bearing power in pounds
W = weight in pounds, of striking part of hammer
H = height of fall in feet

S = the average penetration in inches per blow
S = the average penetration in inches per blow for the last 5 blows for gravity hammers and the last 20 blows for air/steam or diesel hammers

X = weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving



23

# 4. 2015 Standard Specification

Example- 708 Falsework & Form Construction



-Description -Bid Item

#### 708.1 DESCRIPTION

Design and construct safe, adequate falsework to provide the necessary rigidity, support the loads imposed and produce the final structure to the lines and grades shown in the Contract Documents. Falsework is defined to be any temporary structure which supports structural members or form work.

Falsework Inspection

<u>UNITS</u> Lump Sum





Example- 708 Falsework & Form Construction



- Materials

Any grinding needs to be parallel to direction of beams.

Use sound falsework piling to withstand driving, is reasonably straight, and is of sufficient size to provide the strength to safely carry the actual loads imposed. Use sound timber in good condition and free from defects that might impair its strength.


All approved metal or wood forms shall present a smooth surface, be mortar tight and sufficiently rigid to prevent distortion due to the pressure of the concrete and other loads incident to the construction operations, including placement and vibration of the concrete.

Do not use aluminum forms in contact with concrete.



25

# 4. 2015 Standard Specification



Example- 710 Concrete **Structure Construction** 

Fig. 710-1, **Evaporation Rate Chart,** p. 700-42

(Goal is to eliminate plastic shrinkage cracks.)



# 4. 2015 Standard Specification

TABLE 710-1: MINIMUM CURE TIMES AND CURING MEDIUMS						
Type of Work	Minimum Cure Time (days)	Curing Medium and Use				
Bridge decks (full-depth decks with multi-layer polymer overlays)  Bridge subdecks (decks with overlays)	14 Wet	Wet burlap covered with white polyethylene sheeting during the 14-day period.				
Bridge decks (full-depth decks with no overlay) Bridge Overlays	14 Wet Plus 7 Curing Membrane	Wet burlap covered with white polyethylene sheeting during the 14-day period. After the wet cure period, apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat within 30 minutes of removing the sheeting and burlap. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.				
Other unformed or exposed surfaces	7 Curing Membrane	Apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat immediately after completion of the concrete finish just as the surface water disappears. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.  Should the compound be subjected to continuous damage, the Engineer will require wet burlap, white polyethylene sheeting or other approved imperimeable material to be applied at once for the remainder of the cure time.				
Formed sides and ends of bridge wearing surfaces and bridge curbs Other formed surfaces	4 Formed	Formed surfaces will be considered completely cured upon the Engineer's permission to remove the forms, providing the forms have been in place for a minimum of 4 days.  If forms are removed before the end of the 4-day cure period, cure the surface with an application of Type 1-D liquid membrane forming compound.				

Example- 710 Concrete Structure Construction-**TABLE 710-1** p. 700-45 Minimum Cure Times



27

# 4. 2015 Standard Specification

Example- 710 Concrete Structure Construction

# Load Limits on Decks, TABLE 710-2 p. 700-46 Construction loads on the new bridge subdeck, new one-course deck or any concrete overlay are subject to the limitations in TABLE 710-2. The use of supplemental cementitious materials will require additional time before

specified loading is allowed.

TABLE 710-2: CONCRETE LOAD LIMITATIONS ON BRIDGE DECKS							
Days after concrete is placed	Element	Allowable Loads					
1*	Subdeck, one-course deck or concrete overlay	Foot traffic only.					
3*	One-course deck or concrete overlay	Work to place reinforcing steel or forms for the bridge rail or barrier.					
7*. △	Concrete overlays	Legal Loads; Heavy stationary loads with the Engineer's approval.***					
10 *, \(^{\Delta}\) (15)**, \(^{\Delta}\)	Subdeck, one-course deck or post- tensioned haunched slab bridges	<ul> <li>Light truck traffic (gross vehicle weight less than 5 tons).****</li> </ul>					
14 *, \(^{\Delta}\) (21)**, \(^{\Delta}\)	Subdeck, one-course deck or post- tensioned haunched slab bridges	<ul> <li>Legal Loads; Heavy stationary loads with the Engineer's approval.***Overlays on new decks.</li> </ul>					
28	Bridge decks	Overloads, only with the State Bridge					

<sup>\*</sup>Maintain the specified wet cure at all times (TABLE 710-1). \*\* All haunched slab structures



 <sup>\*\*</sup>All haunched slab structures.
 \*\*Submit the load information to the appropriate Engineer. Information that will be required is the weight of the material and the footprint of the load, or the axle (or truck) spacing and the width, the size of each tire (or track length and width) and their weight.
 \*\*\*\*An overlay may be placed using pumps or conveyors until legal loads are allowed on the bridge.
 \( \text{increase time period by 3 days when supplemental cementitious materials are used October 1 thru April 30.

# **All** Specifications

- Read & Review all parts carefully
- When in doubt Ask and Investigate
  - Do not abandon Common Sense

Thanks for Your Attention.



# **CIT Structures**

# **Construction Manual**





1

# Construction Manual - 1

#### **FOREWORD**

This manual has been published to provide construction personnel engaged in inspection activities with a convenient <u>guide</u> for the procedures and methods that are acceptable for the construction of state highway projects under the supervision of the Kansas Department of Transportation.

The procedures, methods and guidelines herein are meant as a guide only and may be modified and/or revised to better fit any given situation or circumstance.

The Construction Manual is not intended as a textbook of highway engineering, but rather as a reference book of guidelines. It is essential that the user have a thorough understanding of the specifications as well as this manual.

Many of the guidelines herein contained are general in character and are not to be construed as replacing, modifying, or superseding any of the provisions of the specifications, plans or contract.

In keeping with the idea that the Highway Construction Industry is an, ever-changing entity, requiring constant re-evaluation of policy and procedures, the format was devised to provide for addition, change, and elaboration of content without the necessity of republishing the entire manual. Each recipient of this manual is requested to suggest needed additions and changes. The suggestions should be submitted through the appropriate channels to the office of the Bureau Chief of Construction and Materials. If revisions are necessary, they will be published by the Headquarters Construction staff and transmitted to the recipients of manuals, whose responsibility it shall be to post these revisions.



- Parts I V
  - Part I General
  - Part II Contract Administration
  - Part III Surveying
  - Part IV Construction Inspection
  - Part V Materials and Testing



3

- Part I General (definitions and outlines)
  - Part 1.03.13 Field Engineer/Manager
    - Supervises and directs the activities of all personnel involved in the construction
  - Part 1.03.14 Project Engineer and Engineering Technicians
    - Directly responsible to the Field Engineer/Manager
    - Supervises and inspects operations
    - Keeps documentation records and makes reports



- Part I General (definitions and outlines)
  - Part 1.04.06 Contractor
    - Proper relations between the Contractor and KDOT personnel are of the utmost importance.
    - Adhere to the plan, specifications and contract requirements, as closely as possible.



5

- Part I General (definitions and outlines)
  - Part 1.04.08 Federal Highway Administration
    - The role of the Federal Highway Administration (FHWA) in relation to federally financed highway construction is to review and require modifications, as necessary, to construction oversight and material acceptance procedures to the extent necessary to be able to provide assurance to Congress that the Contractor constructs these projects in close conformance with approved plans, specifications and change orders.

- Part I General (definitions and outlines)
  - Part 1.05.01 Integrity
    - Absolute integrity on the part of all KDOT personnel is essential to maintain public confidence in KDOT.
  - Part 1.07.01 Safety
    - The Field Engineer and/or Project Coordinator are responsible for providing safety leadership at all time and safety enforcement, when necessary.
    - Safety is everybody's business.



7

- Part II Contract Administration
  - Part 2.04.01 Quantity Changes
    - There are several items of work which are bid on a "planned quantity" basis, and unless either party questions the planned quantity, payment is made on the basis of the planned amount.



- Part II Contract Administration
  - Part 2.07.02 Responsibility, Authority and Behavior of the Inspector
    - The Inspector is responsible for determining that the work is being constructed in accordance with the requirements of the Contract Documents. This does not give the Inspector the right to unnecessarily or willfully disrupt the operations of the Contractor.



9

- Part II Contract Administration
  - Part 2.10.01 Measurement and Payment
    - The Standard Specifications prescribes, in general, how measurements of quantity shall be made.
    - Therefore before making any measurements on a project, the Field Engineer should study the Plans,
       Specifications and Special Provisions to determine first, what is to be measured, and second how it is to be measured.



- Part II Contract Administration
  - Part 2.11.03 Project Diary
    - Documentation Manual & AASHTOWare Project Information.
  - Part 2.11.04 Field Records
    - Documentation Manual & AASHTOWare Project Information.



11

- Part III Surveying
  - Part 3.05.01 Benchmarks
    - Thoroughly check all benchmark elevations before any other level work is started.
  - Part 3.23 Surveys for Structures
  - Part 3.23.01 General
    - In staking out structures, set all lines and measurements absolutely correct.



- Part III Surveying
  - Part 3.23.01 General
    - When possible, completely stake out the entire structure before structure construction begins.
    - Stake the line on the outside of all culverts and multiple-box bridges and offset the stakes a distance sufficient to clear the excavation.
    - Convey the system of staking each pier and abutment to all parties involved in the structure construction.



13

- Part III Surveying
  - Part 3.23.05 Elevations
    - Set at least two benchmarks near each structure.
    - Prior to placing concrete, set molding and check elevation.
    - Also check for elevation after the concrete has been placed, and just before the finishing operation.



- Part IV Construction Inspection
  - Part 4.05 Structures
  - Part 4.05.01 General
    - Review structure plans for possible errors in quantities and elevations.
  - Part 4.05.03 Inspection
    - The Inspector should check all the forms for line, elevation, plumbness, spacing, quality of lumber, bracing, strength, placement of reinforcing steel, etc. before any concrete is placed.



15

- Part IV Construction Inspection
  - Part 4.05.04 Excavation
  - Part 4.05.05 Culvert Foundation
  - Part 4.05.06 Bearing Piles
    - After the Contractor completes the actual pile layout, it should be thoroughly checked by the inspector.
    - Before using any piling, it is the Inspector's responsibility to make certain that the material is tested and that the test reports are on file.




- Part IV Construction Inspection
  - Part 4.05.06 Bearing Piles
    - · a. Pile Lengths
    - b. Test Pile
    - c. Test Pile (Special)
    - d. Log of Continuous Pile Driving for Abutment and Pier Footings
    - e. Pile Driving Hammers
    - f. Driving Pile



17

- Part IV Construction Inspection
  - Part 4.05.07 Drilled Shafts
  - Part 4.05.08 Superstructure
    - a. Falsework Construction
    - b. Structural Steel Construction
    - c. Structure Construction
    - d. Form Removal





		1anual -	エノ					
		Computation	s of Quantities					
	tion Section Title	Pay Item	Unit	Comps	Minimum Measure to Nearest	Minimum Compu to Nearest	te Minimum Pay to Nearest	
Sect 704		Piles (*) (**)	LNFT	Comps	0.1 LNFT	to Nearest	0.1 LNFT	
704	Plling	Test Piles (*) (**)	LNFT		0.1 LNFT		0.1 LNFT	
		Test Piles (Special) (*) (**)	LNFT		0.1 LNFT		0.1 LNFT	
		Cast Steel Pile Points	Each		Each		Each	
		Pre-Drilled Pile Holes	LNFT		0.1 LNFT		0.1 LNFT	
706	Bearings and Pads for Structures	Elastomeric Bearing Pad (**)	Each		Each		Each	
707	Finger Plate and Modular	Bearing (*) (**) Expansion Device (Finger Plate)	Each LNFT		Each 0.1 LNFT		Each LNFT	
707	Expansion Devise	Expansion Device (Finger Plate)  Expansion Device (Modular)	LNFT		0.1 LNFT		LNFT	
708			Lump Sum		Lump Sum		Lump Surn	
710	Concrete Structure Construction	Concrete (*) (**) (***)	CUYD	Х	0.1 FT	0.1 CUYD	CUYD	
711	Reinforcing Steel	Reinforcing Steel (*) (**)	LBS	Х	0.1 FT	1 LB	10 LBS	
712		Reinforcing Steel (Repair) (*) (**) (Set Pri	e) LBS	X	0.1 FT LB	1 LB	10 LBS	
/12	Structural Steel Construction	Structural Steel (*) (**) (***) Structural Steel (Merchant Quality)	LBS		LB		LB	
		Welded Stud Shear Connectors	Each		Each		Each	
		Bridge Drainage System	Lump Sum		Lump Sum		Lump Surn	
			LNFT		0.1 LNFT		LNFT	
			Each		Each		Each	
714	Painting Structural Steel	Bridge Painting (*)	LBS Lump Sum		LB Lump Sum		LB	
/14	Painting Structural Steel	Environmental Protection	Lump Sum		Lump Sum		Lump Surn	
		Power Wash	Lump Sum		Lump Sum		Lump Surn	
715	Prestressed Concrete Members	Prestressed Concrete Beams (*) (**)	LNFT		0.1 LNFT		LNFT	
		Prestressed Concrete Panels	SQFT	X	0.1 FT	0.1 SQFT	SQFT	
716		Post - Tensioning for Slab Bridge						
717	Bridges)	Cilian Surra Country (8) (88)	LBS	×	LB 0.1 FT	0.1 SQYD	LB SQYD	
717	Silica Fume Overlay	Silica Fume Overlay (*) (**) Material for Silica Fume Overlay (Set Price	CUYD	x	0.1 FT	0.1 CUYD	CUYD	
719	Expansion Joint (Strip Seal	Expansion Joint (*)	LNFT		0.1 LNFT	0.1 0010	LNFT	
	Assembly)Preformed Elastomeric							
	(Neoprene & Compression &							
721	Other) Handrail for Bridges & Other Uses	Bridge Handrail (*) (**)	LNFT		0.1 LNFT		LNFT	
721	Handrail for Bridges & Other Uses	Handrail (*) (**)	LNFT		0.1 LNFT		LNFT	
722	Sign Structures & Bridge Mounted		Each		Each		Each	
	Sign Attachments	Butterfly Overhead Sign Structure(*)(**)	Each		Each		Each	
		Cantilever Sign Structure(*)(**)	Each		Each		Each	
		Overhead Sign Structure(*)(**)	Each		Each		Each	
		Overhead Sign Structure (Mast Arm						T 7
		Type)(*)(**)	Each		Each		Each	

Computations of Quantitie

Section	Section Title	Pay Item	Unit	Comps	Minimum Measure to Nearest	Minimum Compute to Nearest	Minimum Pay to Nearest
722	Sign Structures & Bridge Mounted	Overhead Sign Structure (Single Tapered					
	Sign Attachments (cont.)	Tube)(*)(**)	Each		Each		Each
		Remove and Reset Sign Structure (***)	Each		Each		Each
		Reset Sign Structure (***)	Each		Each		Each
		Sign Structural Modification (***)	Each		Each		Each
723	Substructure Waterproofing	Substructure Waterproofing Membrane					
	Membrane		SQYD	X	0.1 FT	0.1 SQYD	SQYD
724	Bridge Backwall Protection System	Bridge Backwall Protection System	SQYD	X	0.1 FT	0.1 SQYD	SQYD
725	Abutment Drainage Systems	Abutment Strip Drain	SQYD	X	0.1 FT	0.1 SQYD	SQYD
726	Concrete Masonry Coating	Concrete Masonry Coating	SQYD	X	0.1 FT	0.1 SQYD	SQYD
727	Repair (Structure)	Bridge Repair	Lump Sum		Lump Sum		Lump Sum
		Jacking of Existing Structure	Lump Sum		Lump Sum		Lump Sum
		Raise Expansion Device	Each		Each		Each
		Remove and Reset Expansion Device	Each		Each		Each
		Reset Existing Bearing	Each		Each		Each
728	Bridge Curb Repair	Bridge Curb Repair	LNFT		0.1 LNFT		LNFT
729	Multi-Layer Polymer Concrete	Multi-Layer Polymer Concrete Overlay					
	Overlay		SQYD	X	0.1 FT	0.1 SQYD	SQYD
730	Epoxy Resin Crack Repair	Epoxy Resin Crack Repair	LNFT		0.1 LNFT	100000000000000000000000000000000000000	LNFT
731	Area Prepared for Patching	Area Prepared for Patching	SQYD	X	0.1 FT	0.1 SQYD	SQYD
	(Existing Concrete Bridge Decks)	Area Prepared for Patching (Full Depth)	SQYD	×	0.1 FT	0.1 SQYD	SQYD
		Area Prepared for Patching (Poured with					
		Overlay)	SQYD	X	0.1 FT	0.1 SQYD	SQYD
		Reinforcing Steel (Repair) (*) (**) (Set Price)	LBS	×	0.1 FT	1 LB	10 LBS
732	Machine Preparation (Existing	Machine Preparation (*)	Name of the last o	1000	and the second second	many and a second	CROSCOV N
	Concrete Bridge Decks)		SQYD	X	0.1 FT	0.1 SQYD	SQYD
733	Hydrodemolition	Hydrodemolition	SQYD	X	0.1 FT	0.1 SQYD	SQYD
734	Structural Plate Structures	(*) Structural Plate Pipe (**) (***)	LNFT		0.1 LNFT		LNFT
		(*) Structural Plate Pipe Arch (**) (***)	LNFT		0.1 LNFT		LNFT
		(*) Structural Plate Arch (**) (***)	LNFT		0.1 LNFT		LNFT
735	Precast Reinforced Concrete Box	Reinforced Concrete Box (*) (Precast)	LNFT		0.1 LNFT		LNFT
07-07001	Bridge Project Marker	Bridge Project Marker	Each		Each		Each
07-07003	Heat Straightening (In-Place) of Damaged Structural Steel	Heat Straightening Repair	INFT		0.1 LNFT		INFT
07-07012	Expansion Joint (Membrane	Expansion Joint (Membrane Sealant *)	Livi i		0.2 0411		Little 1
	Sealant)		LNFT		0.1 LNFT		LNFT
07-07018	Rolled Beam Detour Bridge	Erect and Remove Rolled Beam Detour					
		Bridge	Lump Sum		Lump Sum		<b>Lump Sum</b>
		Furnish Rolled Beam Detour Bridge	Lump Sum		Lump Sum		Lump Sum

Page 6 of 14



21

- Part V Materials
  - Section 5.1 General
  - Section 5.2 Quality Control/ Quality Assurance
  - Section 5.3 Mix Design Methods
  - Section 5.4 Laboratory and Sample Identification
  - Section 5.5 Required Sample Sizes
  - Section 5.6 Aggregates
  - Section 5.7 Inspection and Sampling of Materials
  - Section 5.8 Nuclear Gauge



- Part V Materials
  - Section 5.9 Sampling and Test Methods Forward
    - 5.9.17 KT-17 Sampling Freshly Mixed Concrete
    - 5.9.18 KT-18 Air Content of Freshly Mixed Concrete by the Pressure Method
    - 5.9.20 KT-20 Mass Per Cubic Foot (Meter), Yield and Air Content (Gravimetric) of Freshly Mixed Concrete
    - 5.9.21 KT-21 Slump of Portland Cement Concrete
    - 5.9.23 KT-22 Making and Curing Compression and Flexural Test Specimens in the Field



23

- Part V Materials
  - Section 5.10 Calculations
  - Appendicies
    - Appendix A Sampling and Testing Frequency Chart Non-Quality Control/Quality Assurance
      - Appendix A is found in the back of the Part V, along with appendix B,C and D



# CONSTRUCTION Manual - 24 SAMPLING AND TESTING PROJUENCY CHART NON QUALITY CONTROLOGULARY ASSERANCE SPECIFICATIONS CONSTRUCTION OR NATURAL TYPE 1918 54d, Spec. (SS 2015) INTEND SPECIFICATION CONDITION SPECIFICATION CONDITION SPECIFICATION COMPLETE AND INSERTING PROJUENCY COMPLETE AND INSERTING PROJUENCY COMPLETE AND INSERTING PROJUENCY COMPLETE AND INSERTING PROJUENCY CONDITION OF THE PROJUENCY CONDITION OF

CONSTRUCTION OR AND TESTING PROQUENCY CHART


NON OUALITY CONTROLOGUALITY ASSERANCE SPECIFICATIONS


CONSTRUCTION OR AND TESTING PROQUENCY CHART


NON OUALITY CONTROLOGUALITY ASSERANCE SPECIFICATIONS

CONTROL TO BE SHEET OF THE S

25







# **CIT Structures**

# **Documentation**





1

# 1.Documentation

- Definition
  - Source
    - Merriam-webster.com
      - The documents, records, etc. that are used to <u>prove</u> something or make something official
    - Dictionary.com
      - The use of documentary evidence





- What is to be documented?
  - Everything
    - Conversations; If you stated it or heard it, document it. Relevant to the contract documents. <u>Facts only!</u> No thoughts, opinions or hearsay.
    - Measurements; Actual and that which are physically conducted or calculated.
    - Length, width, depth
    - Feet, square feet, square yards, cubic yards
    - Pounds, tons
    - Equipment and personnel



- How is to be documented?
  - Documentation Manual
    - I. Purpose: A uniform method, greater efficiency
    - II. **Scope:** Manual demonstrates by example, minimum reporting requirements
    - III. Definitions:
      - A. Field Book: A permanently bound book used for the entry of information. A computer is not considered a field book.

5

- How is to be documented?
  - Documentation Manual
    - III. Definitions:
      - D. Source Document: Any permanent record inscribed showing the origin of the information itself and such data. i.e. A Field Book:






7.Documentation

How and Where do I document?

Field Books


AWP (AASHTOWare)





- **Diary** AWP and field books should only have 4 things:
  - Weather
  - Day Charged if contractor worked
  - In the remarks, the Type should be "A-Project Diary, and the remarks box should only have either: "See DWR" if contractor worked or "Contractor did not work due to (reason)"
  - Controlling Operation Drilled Shafts (usually taken from contractor's schedule)






<u>DWR (Daily Work Report)</u> in AWP but in a field book also – Should have all other pertinent information as shown in the AWP user guides and documentation manual.

- A Partial list of items to be noted in DWR's and Field Books
  - Orders given the contractor, and whom the order was given
  - · Important discussions with the contractor
  - Equipment Used
  - Personnel on the project
  - · Official Visitors and Inspections
  - Work or material rejected, and reasons
  - · Time of shutting down or resuming of work, and explanations
  - · Work done by contractor's forces during the day.
  - · General purpose of work
  - Account of any time by contractor's personnel and equipment on disputed items of work.
  - · Length and cause of any delays.
  - · Arrival and departure of major equipment.
  - · Record of telephone calls
  - Unusual conditions, if any, such as high water, bridge failures or slides.
  - Progress of staking and surveys made.

Many more then I could list





- Documentation Manual
  - IV. Introduction to General Index: The Index is broken down into separate divisions coinciding with the 2007 Standard Specification for State Road and Bridge Construction. Each division is further broken down into various example plates.



15

- Documentation Manual
  - V. Documentation of Field Records: Documentation shall be made to substantiate payments. All field book entries should be made using 2H lead. Original entries, later determined to be error, shall not be erased. A line should be drawn through the incorrect details and the correct details should be entered directly above the stricken material. All corrections and reference notations should have the initials of the person making the corrections and notations.



#### GENERAL INDEX

Division 100 - General
Index to Field Books
Inspector Verification
List of Contractor's Equipment
List of Contractor's Personnel

**Division 150 Equipment** 

Division 200 - Earthwork

Division 300 - Stabilized Subgrade, Base and Shoulders

Division 400 - Concrete

Division 500 - Rigid Pavement

**Division 600 - Flexible Pavement** 

Division 700 - Structures

**Division 800 - Incidental Construction** 

<u>Division 900 - Roadside Improvement</u>

Source Documents for Pay Quantities

Computations of Quantities (Measure to - Pay to)



17

- Section 700
  - Documentation Manual \_ Drilled Shaft

RECORD	CORD OF DRILLED SHAFTS Br. No 16.41 Abut. No					
		Measured	Plan	Measured	Vertical	Date
Shaft	Plan	Diameter	Depth	Depth	Alignment	Checked
No.	Diameter	Shaft	Shaft	Shaft	Check	Insp.
			PERATION			
	TO VERIFY	Y THE ACC	EPTABILIT	Y OF THE V	VORK	
	COMPLET	ED. THIS C	CHECK IS B	ACKUP DA	TA FOR	
	INFORMAT	TION SHOW	VN ON THE	"RECAPITI	JLATION	
	OF DRILLE	D SHAFTS	COMPLET	ED".		
		eet and inch				
	weurc =(m	eter and mil	iiiieters)			



- Section 700
  - Documentation Manual \_ Drilled Shaft

	Shaft	Measured	Plan	Pay	Accum.	Date		Reference		
Location	No.	Length	Length	Length	Pay	Completed	Insp	Bk / Pg	Remarks	



19

- Section 700
  - Documentation Manual \_ Piling

Date CMS Heat Number Quantity Field Number Quantity  Checked ID Number of Pieces (Lin. Ft.) Ident. of Pieces (Lin. Ft.) (Lin. Ft.)		Date	
		Date	
Checked ID Number of Pieces (Lin. Ft.) Ident. of Pieces (Lin. Ft.) (Lin. Ft.)	INSP		
		Used	INS
		<u> </u>	
	_		



- Section 700
  - Documentation Manual \_ Piling

OCATION	: PIER NO. 1	DATE 6/15	5/2002	TY	PE OF HAN	MER: DELM	AG DIESEL	(D-12)	
M 2 3.5	1 1252.67		12	249.16 TY	PE OF PILE	E: HP 12 x 53			
IER 1 HUE	3 B		3.48 1	249.16 W	EIGHT OF H	AMMER: 82	50		
OMPUTA	TION FORMU	JLA USED:		W	EIGHT OF	CAP: 1740			
P =	2 x W x H x	0.80			F	LAN LENGT	H OF PILING	G: 87 LIN. FT.	
	S + 0.1 (X /	W)				WEIGHT OF	PILE PER I	LIN. FT. 53 LBS	
				Distance			Computed		
		Blows	Point of	of Tip	Drop	Average	Bearing		
Pile	Cutoff	Per	Pile	Below	of	Penetration	Power		
Number	Elevation	Foot	Elevatioin	Cutoff	Hammer	in Inches	in Tons	Remarks	Insp



21

- Section 700
  - Documentation Manual \_ Piling

		Length	Accum		Accum		Accum	Pile	ber			
	Pier or	Ordered	Length	Length	Length	Length	Length	5	Number	Re	fer	
	Abut	and	Ordered	of Pile	of Pile	of Pile	of Pile	Number Splices	Accum Nu of Splices	BK.	PG.	
Date	Number	Accepted	& Acc.	in Place	in Place	Cut off	Cut off	Nun Spli	Acc	NO.	NO.	Insp



- Section 700
  - Documentation Manual \_ Reinforcing Steel

Reinforci	ng Steel Ch	eck	ı	ı	ı				
Date		Size		Spa	cing	Clea	rance		
Checked	Bar	Plan	Actual	Plan	Actual	Plan	Actual	Remarks	Insp.

Note: In order to be assured that the reinforcing steel in a structure is placed in conformance with the plans and specifications, an actual count of the bars and measurement checks of the spacing is required, however; in many cases it is not possible t





23

- Section 700
  - Documentation Manual \_ Concrete Testing

	CONCRET	E TEST DA	TA -							
Date										
Time										
Station										
Theo.Wt. Per Cu. Ft.										
Wt Bucket, Conc & Glass										
Weight of Bucket and Glass										
Meas. Wt										
Corr Factor										
Corrected										
Weight					This plate i	s an operati	onal record	of the tests	performed	
/Cu.Ft.					during the	placement o	f the concre	te pavemer	nt.	
Weight										
Difference										
% Air										
Slump										











Bridge Construction Manual

1

# **Locating Bridge Construction Manual**

- Where do you find the Bridge Construction Manual?
- It is housed in the KDOT Bureau of Structures and Geotechnical Services home page under 'Fabricator Information'
- The direct link is:

   https://www.ksdot.gov/doing business/highway contractors/contractor resources/bridge-construction manual

#### **Fabricator Information**

- Future Steel Bridge Projects
- Future Prestressed Bridge Projects
- Future Post-tensioned Slab Bridge Projects
- Superstructure Codes
- Steel Fabricator Shop Capabilities
- Shop Welding Procedures
- Bridge Construction Manual
- <u>KDOT Bridge Design Manual (LFRD)</u> (KART)



# **Bridge Construction Manual 1**



**5.3 DRIVEN PILE** Table of Contents 5.3.2 Bid Items 5.3.3. Types of Piles ...... 5.3.4 Pile Driving Equipment 5.3.4.3 Types of Hammers:
5.3.4.4 Power for Hammers:
5.3.4.5 Diesel Hammer Terminology:
3.5 KDOT Specifications for Hammer Sizes: 5.3.6 Pile Driving Mechanics: 5.3.6.1 Reviewing the Information on the Plans: 5.3.6.2 Preparing to Drive Pile 5.3.6.3 During the Drive 5.3.3.1 Basis of Acceptance (Materials) ... .3.3.2 Pile Order Lengths 5.3.7 Pile Restrike 5.3.7 Pile Restrike
5.3.8 Log of Pile Driving
5.3.8.1 As-Built Geology
5.3.8.2 Pile Driving Formulas
5.3.8.3 Field Pile Driving Guide
5.3.9 Hammer Data Kansas

3

# **Bridge Construction Manual 2**

#### **5.3 DRIVEN PILE**

#### 5.3.1 General

Driven piles are used as the foundation for almost all abutments in Kansas bridges. Likewise they are used as the foundation for many piers in Kansas bridges. Proper pile driving inspection is critical to a successful bridge project.

There are two types of driven piles: sheet pile and foundation pile. Sheet piles are long, interlocking, rolled steel plates used in retaining structures, such as walls and cofferdams. Foundation piles are long slender columns designed to be driven into the ground. Foundation piles will be discussed here.

will be discussed here. Foundation piles are simply columns, designed to transmit surface loads to low lying soil or bedrock. These loads are transmitted by friction between the pile and ground and by point bearing through the end of the pile. The actual amount of frictional resistance or end bearing is dependent on the particular site conditions. Foundation piles are made of steel, concrete, or timber. Of these materials, steel H-pile and castin-place pipe pile are most commonly used in Kansas. The material and size of pile to be used on a particular project are designated in the plans on the General Notes and Summary of Quantities Sheet.

Piles are used when a deep foundation is necessary. This is the case when the soil near the surface is unsuitable to carry the loads imposed by the structure. Piles are also used when the possibility exists that the soil under the foundation may be washed away.

Steel Piles: Steel piles are generally rolled H-pile used in point bearing. H-pile are available in many sizes, and are designated by the depth of the member and the weight per unit length. For example, an HP 12X74 is an H-pile which is 12" deep and weighs 74 pounds per foot. H-piles are well adapted to deep penetration and close spacing due to their relatively small point area and went adaptice to eleep penetration and close spacing due to their relatively simal point area and small volume displacement. They can also be driven into dense soils, coarse gravel and soft rock without damage. In some foundation materials, it may be necessary to provide pile points (Figure 2) to avoid damage to the pile. In some instances it may become necessary to increase the length of H-Pile by welding two pieces together. If this is the case, splicing must be done in accordance with KDOT specifications.

KDOT primarily utilizes Steel H-Pile. However, the following types of pile may be used on

<u>Cast-in-place pipe pile</u>: Cast-in-place pipe pile are considered as displacement (friction) type pile. Closed-end pipe piles are formed by welding a watertight plate on the end to close the tip end of the pile. The shell is driven into the foundation material to the required depth and then filled with concrete. Thus both concrete and steel share in supporting the load. After the shell is driven and before filling with concrete, the shell is inspected internally its full length to assure that damage has not occurred during the driving operation. Pipe pile may be either spiral or longitudinally welded or seamless steel. Pipe piles are normally used in foundation footings. Their use for above ground pile bents is not recommended. Pipe pile are considered concrete pile for bidding and on the Standard Pile sheet.



# **Bridge Construction Manual 3**

Kansas Department of Transportation

Bridge Construction Manual

# 8.0 REINFORCED CONCRETE STRUCTURES

#### Table of Contents

8.1 General
8.2 Purpose
8.3 Description
8.3.1 Bid Items
8.3.2 Terms
8.3.3 General Concrete Concerns
8.4 Materials
8.4.1 Concrete
8.4.2 Reinforcement
8.4.2.1 Phased Construction Reinforcement
8.4.3 Formwork and Falsework
8.4.4 Waterproofing
8.4.5 Strip Drains
8.4.6 Curing and Protection

8.5 Construction Procedures	
8.5.1 Forms	
8.5.2 Reinforcement Placement	
8.5.3 Concrete Placement and Finishing	1
8.5.4 Mix Designs and Testing	1
8.5.5 Consolidation	
8.5.6 Slip forming	1
8.5.7 Surface Finish	1
8.5.8 Joints	1
8.5.9 Evaporation and Fogging	1
8.6 Concrete Construction Specifications	2
8.6.1 Minimum Cure Time	
8.6.2 Maximum7 Load Limits	
8.6.3 Minimum Strength Gain	2
8.6.4 Measurement and Payment	2
8.6.5 Field Testing & Concrete Batch Rejection	2
8.6.6 Ternary Mix Designs	2
Mix Design Examples	2
General Concrete Structure Checklist	2



5

# **Bridge Construction Manual 4**

Kansas Department of Transportation

Bridge Construction Manual

#### 8.6.5 Field Testing & Concrete Batch Rejection

A global "rule of thumb" does not necessarily exist to decide when the failure of a field test should be used to reject a batch of concrete because of the various structure types, concrete types, and the severity level of each test result. For example, if a test of air-entrained concrete for a pileacp resulted in 4.9% air (requirement is 6.5 ±/- 1.5%), but all other tests were within tolerance, it would not be standard procedure to reject the entire load of concrete. The inspector could instead call the plant and draw attention to the need for slightly more air, and allow placement of the concrete. However, if the air result was 9.0% and the density of the concrete was 135 lbs/ft², the load would be a firm candidate for rejection as two items are well outside the tolerance range for air and for density. That being said, it is not unreasonable to expect the first batch of concrete arriving on site to meet all specification requirements. Genesity, air, slump, etc. The supplier needs to prove to the inspector they are capable of meeting all of the specification requirements and all of the requirements listed in the mix design. The level of quality of the concrete needs to first be established by the supplier before it is relied upon. It needs to be understood that KDOT will not sacrifice quality by letting the first few trucks act as the test batches to fine tune the final mix for the rest of the structure. Sub-standard concrete at the outset of a pour is not acceptable.

The concrete pour shall be planned as such that the total revolutions on the truck, concrete temperature, ambient temperature, can all meet section 401.8 of the KDOT specifications.

If the very first batch of concrete to arrive on site meets all specification requirements stated for the concrete, then testing taking place at regular intervals throughout the rest of the pour is simply verification of previous results. Testing during the middle of a pour takes place while the batch is being placed in the structure. Since the tests require a fair amount of time to complete, most of the batch of concrete is in the structure before test results are available.

If a test fails for a batch of concrete, it needs to be well documented and cylinders need to be made. Making cylinders and clearly documenting where the concrete was placed in the structure will provide a method to verify the final strength and durability of the cured concrete and will pinpoint the location of the concrete if the quality is low enough to require the contractor to remove the substandard concrete and replace with quality concrete. Making cylinders benefits both the contractor and KDOT. At times, cylinders are used to quantify the quality of questionable concrete, possibly allowing the contractor to leave the concrete in place because it has met minimum expectations for KDOT.. It is vital the cylinders be cured under the same conditions as the concrete in the structure. If blankets have been placed to protect the structure concrete from the elements, the cylinders must be placed under the blankets, as well. This is commonly overlooked, but very important. If the cylinders are not cured under the same conditions as the concrete in the structure, they become an inaccurate representation of the concrete in the structure.




# **Bridge Construction Manual Overview**


- Offer commentary on KDOT specifications
- Highlight good practices
- Introduction for inspectors, and designers
  - Pile Driving worked examples
  - · Drilled Shaft guidance
  - Traps to avoid/be aware of during construction
- Only chapters with active hyperlinks are available
- Feel free to contact the instructors for structure related questions or guidance
- New Manual Under Review





# **Project Plan Sheets**

PL-1









# **General Notes & Quantities**

EMBANKMENT: Complete the embankment of the abutments as shown on a Bridge Excavation sheet prior to driving the abutment piling or

BRIDGE EXCAVATION: Elevation 1092.90 shall designate the Excavation Boundary Plane of Class I and Class II Excavation; Class I above the plane, Class II below the plane. See the Bridge Excavation sheet for to limits of pay excavation.

 ${\it BACKFILL\ COMPACTION:\ Compact\ backfill\ at\ the\ abutments.}$ 

PILING: Drive all piling to bear upon the limestone of the Neva Member.
Driving shall stop when in the opinion of the Engineer additional driving may demape the piling. Drive all piling to the Pile Driving Formula Lon of:
Abutment \*!: 154 Tons

As a minimum drive each pile to the load and penetration, but in no case shall the pile to driven to mere than 100X of Pile Driving Formula Driving Load. At any location where problems are experienced pile damage is suspended, or the Pile Driving Formula Load cours significantly above the design pile tip elevation, the Engineer may reque that the Pile Driving Analyzer (PDA) equipment be used.

REMOVAL OF EXISTING STRUCTURES Removed of existing structure is included in the bid frem. Removal of Existing Structures\*, Lung Sum. With the exceeding of the steel cover picture over the rockney, and the zirides pumble; allow of investic is removed from the existing structure the site. Steel cover pictus and bridge number, picte, shall be retained by KDDT.

EXISTING STRUCTURE: Plans of the existing structure are on file and available for inspection by qualified bidders at the State Bridge Office KDOT. Eisenhower State Office Building, 700 SW. Harrison, Topeta, KS

BROKEN CONCRETE: Waste the broken concrete from the existing bridge on sites provided by the Contractor and approved by the Engineer.

DEMOLITION PLANS: This is a Category A Demolition. Submit detailed Demolition Plans to the Field Engineer per KDDT Specifications, No Demolition work will begin without approved Demolition Plans. A Licensed Professional Engineer is not required.

SLUPE PROTECTION (reprap Stone) Place Stope Praection (reprap Stone to the limits and thicknesses shown on the plans or as directed by the Fingineer.

REINFORCING STEELs All reinforcing steed dimensions are to the centerline of bors unless atherwise nedes, All reinforcing steel, except the spiral bors, shall conform to the requirements of ASTM A615, Grade 60. Spiral bors may meet the requirements of aFTM A615, Grade 60. Spiral bors may meet the requirements of after ASTM A615, Grade 60. or 60) or A82, and are included in the bid item "Reinforcing Steel (Gr. 60)".

nd the coded.

CONCRETE: Superstructure concrete is bid as Concrete Grade 4.0(AEI/SA).

Substructure concrete is bid as Concrete Grade 4.0/AEI, If desired,
the Contractor may use Concrete Grade 4.0 in the footings and in the
abufments below the construction faint. Been dell exposed edges of all

PLACING SEQUENCE. The Contractor will adhere to the placing direction/ sequence sharm on the plans. Changes will be accepted only if the Contractors Engineer of Justs the chanter-diagram so that the fobricator can of Just the web Catabor and headed sid another heights accordingly, deep the plant of deet faming, if graftle grinding decreases the cherance to the top and of reinforcement to less than 2½'z a players certify will be placed of

CONCRETE PLACING: Place and hand vibrate all concrete for Abutment #1 above the construction joint to the bottom of deck elevation just prior the normal poving train appearations. Do this work in a manner to avoid could loids in atther the slab or in Abutment #1. CONSTRUCTION LOADS: Only foot traffic is permitted on the new sub-deck, one-course deck or any concrete overlay during the seven day curing period, keep any exposed deck wel during the 7-day curing period. See KDOT Specifications.

ABUTMENT STRIP DRAIN: See the General Notes on the "Abutment Strip Drain" sheet.

BRIDGE BACKWALL PROTECTION SYSTEM: See the General Notes on the "Abulment Strip Draint sheet."

QUANTITIES: Items not listed separately in the Summary of Quantities are subsidiary to other items in the proposal.

TEMPERATURE: The design temperature for all dimensions is 60°F.

dimensions unless atherwise noted. Make necessary allowances for roadway grade and cross slope.

GOVERWENT BENCH WARKS: Preserve any National Geodelic Survey bench marks that are located on the project. Notify, Mr. Monroe Rivers, NOS State Geodelic Advisor, Bureau of Design, KCDT, at (195):296-6935, if any government bench warks are in danger of being destroyed due to construction. Natification shall be given 30 days prior to the start of construction. The National Geodelic Survey will send personnel to relocate to the property of the send of the


the broom mark or issue instructions concerning its reactions.


AGRIG STATION Privale the littled States Geological Geologic


U.S. Geological Survey 4821 Quail Crest Place Lawrence, KS 66049-3839

(Not always the same on each Project so take your time and read each carefully)





























#### (Project Alignment & Geometry)



Elevations



15

# Abutment Strip Drain

BUTMENT STRIP DRAIN; The Bridge Controctor shall excovate to the limits shown on the Bridge Excovation sheet, grade the bottom of the bookfill area, place the strip drain, and place the perforated pips, the outled pips, the CUMP, and the bookfill. Guide post and coarse aggregate are <u>subsidiary</u> to this bid item. Guide post and coarse aggregate are not required if the CMP emplies aftor largo.

BRIDGE BACKWALL PROTECTION SYSTEM: Apply a Bridge Bookwall Protective System to the approach side of the abutments and the wings in accordance with KDDT Specifications and If manufacturer's recommendations. Cover the abutments and wings to the limits shown on the defails. Prior to backfilling, repair any damage dane to the system of no charge to the state,

Place perforated pipe next to the strip drain. Use non-perforated pipe outside the limits of the strip drain. Enclose the perforated pipe with the extension of the filter fabric.

Compact the abutment backfill. See the KDOT Specifications

Perforated pipe and non-perforated outlet pipe shall be corrugated polyethylene tubing conforming to the KDOT Specifications.

Fit the CMP end section with  $\frac{1}{4}$  galvanized mesh screen to prevent the entrance of rodents. Seal the Joint between the outlet pipe and the end section with a Joint sealer. Place coarse aggregate at the outlet and as shown.


Grade the bottom surface of the excovated area to drain. Bockfill this area with a cohesive type soil. The soil should be a sith clay or clay under the Kansas Classification System with a minimum plasticity index of 13. Compact the material to Type B standards.


Place the outlet pipe on the downstream side of structures over streams and as shown or noted on other crossings (See the "Construction Layout" sheet).


Estand filter febric backing of and lay a minimum of 6	
Strip Drain (Boad to Abutment)  Bookfill Composition  - Bookfill Composition  See Standard Specification	
# E Cahesive soi!    Type B Compage   Cahesive soi!	
Trend filter febric booking   Arminism of E  Backeting of injurious of E  Backeting of a Perforated Spee to Drain 11X grade minimum Spee to Drain 11X grade minimum	

SUMMARY OF QUANTITIES (Abutment #1	
Abutment Strip Drain	X Sq. Yds.
Bridge Backwall Protection System	X Sq. Yds.
Items <u>Subsidiary</u> to Strip Drain	
4" Ø Perforated Pipe	38 Lin. Ft.
4" Ø Outlet Pipe	26 Lin. Ft.
6' Ø CMP	8 Lin. Ft.
Items <u>Subsidiary</u> to Slope Protection	(Shot Rock)
Genteytile Eghric	X Sa. Yds.









































#### Steel Erection, Fit-up and Bolting DT I Washer Bolt End Steel Plate May be 5 or 6 protrusions depending on manufacturer and bolt size. Feeler Gage Placed in the gap between protrusions at the indentation marks Protrusions REQUIRED MARKING DETAIL (shows calibrated turn - 31/2 Elevation flats from snug tight condition). Example only, calibrated turn may TYPICAL DIRECT TENSION INDICATOR (DTI) be more or less than shown. Kansas
































### **Final Thoughts:**

Bridge Plans contain a lot of information – some of which is record keeping (hydraulics, scour, As-built changes, revisions, etc.) some of which is for initial construction.

Currently there are only 3 Bridge Squads. Maintenance Plans are handled by a consultant sitin, so if you ever have questions, or see something that doesn't quite add up, just email or call.

Thanks & Good Luck!!!







### Concrete and Reinforcing Steel

1

### **Concrete – Division 400**

### TABLE OF CONTENTS

#### DIVISION 400 CONCRETE

SECTION	PAG
401 - GENERAL CONCRETE	400-
402 - STRUCTURAL CONCRETE	400-14
403 - ON GRADE CONCRETE	400-1
404 - CONCRETE FOR PRESTRESSED CONCRETE MEMBERS	400-2
405 - CURING ENVIRONMENT	400-2

### 400 - Concrete

Specification Number	Title	Section
<u>15-04001</u> *	Kansas City Metro Materials	400
15-04002	Structural Concrete	402
15-04002-R01*	Structural Concrete	402
<u>15-04003</u> *	On Grade Concrete	403
<u>15-04004</u> *	Concrete Prestressed Concrete Members	404
15-04005	General Concrete	401
15-04005-R01	General Concrete	401
15-04005-R02	General Concrete	401
15-04005-R03	General Concrete	401
15-04005-R04*	General Concrete	401

\*Latest version of special provision



### What is Concrete?

Concrete (Division 400)

### 401.2 MATERIALS

Provide materials that comply with the applicable requirements.

ggregate	
dmixtures and Plasticizers	
rade 2 Calcium ChlorideDIVISION 1700	
ement, Fly Ash, Natural Pozzolans, Silica Fume, Slag Cement and Blended Supplemental	
ementitious	
Vater DIVISION 2400	

- Strong in compression but weak in tension
  - Reinforcing Steel is designed to carry tension forces that concrete cannot resist on its own.



3

### **Concrete Grade**

- Refers to the required 28 Day compressive strength
- Grade selected based on structural demand
- Grade 4.0 is the most common for reinforced concrete structures.

TABLE 401-3: CONCRETE STRENGTH REQUIREMENTS Specified 28 Day Compressive Strengths, minimum, psi f'c					
Grade 7.0	7,000				
Grade 6.0	6,000				
Grade 5.0	5,000				
Grade 4.5	4,500				
Grade 4.0	4,000				
Grade 3.5	3,500				
Grade 3.0	3,000				
Grade 2.5	2,500				



### **Concrete Classification**

- (AE)
  - Air-Entrained Concrete
- (AE)(SW)
  - Select Coarse Aggregate for Wear
- (AE)(SA)
  - <u>Select Coarse Aggregate for wear and Absorption</u>
- (AE)(AI)
  - Select Coarse Aggregate for wear and <u>Acid Insolubility</u>
- (AE)(PB)
  - Select Coarse Aggregate for use in <u>Prestressed Beams</u> *Division 1100 Aggregates*



5

### Cement

- Structures will generally be dealing with the center row
- High Early Strength Concrete may be well suited for accelerated bridge projects
- Cements of differing types and or sources cannot be intermixed within any singular component of a structure.

Concrete for:	Type of Cement Allowed		
On Grade Concrete	Type IP(x) Portland-Pozzolan Cement		
	Type IS(x) Portland- Slag Cement		
	Type IT(Ax)(By) Ternary Blended Cement		
	Type IL(x) Portland-Limestone Cement <sup>1</sup>		
	Type II Portland Cement		
All Concrete other than On	Type I Portland Cement		
Grade Concrete.	Type IP(x) Portland-Pozzolan Cement		
	Type IS(x) Portland- Slag Cement		
	Type IT(Ax)(By) Ternary Blended Cement		
	Type IL(x) Portland Limestone Cement <sup>1</sup>		
	Type II Portland Cement		
High Early Strength Concrete	Type III Portland Cement		
	Type I, IP(x), IS(x), IT(Ax)(By), Type IL(x)1 or II		
	Cement may be used if strength and time		
	requirements are met.		



### Structural Concrete Specific Requirements

- Maximum water to cementitious ratio of 0.45 and a minimum cementitious content of 480 lbs per cubic yard.
- Air entrained concrete with a target air content of 6.5 ± 1.5 percent as specified in subsection 401.3i.
- See subsection 402.3e for additional requirements



7

### **Structural Concrete Slump**

### Subsection 402.3f

#### f. Slump.

- (1) Designate a slump for each concrete mix design that is required for satisfactory placement of the concrete application. Reject concrete with a slump that limits the workability or placement of the concrete.
- (2) If the designated slump is 3 inches or less, the tolerance is ±3/4 inch, or limited by the maximum allowable slump for the individual type of construction.
  - (3) If the designated slump is greater than 3 inches the tolerance is ±25% of the designated slump.
- (4) For drilled shafts the target slump just prior to being pumped into the drilled shaft is 9 inches. If the slump is less than 8 inches, redose the concrete with admixtures as permitted in subsection 401.3k.



### **Slump Tolerances**

- Example #1
  - The Specified Slump = 4"
  - 4" > 3"  $\rightarrow$  Tolerance is  $\pm$  25%
    - 4" x 25% = 1"
    - 4" 1" = 3"
    - 4" + 1" = 5"
    - The acceptable range is 3" to 5"
- Example #2
  - The Specified Slump for a Bridge Deck = 21/4"
  - $2\frac{1}{4}$ " < 3"  $\to$  Tolerance is +  $\frac{3}{4}$ "
    - $2\frac{1}{4}$ "  $\frac{3}{4}$ " =  $1\frac{1}{2}$ "
    - $2\frac{1}{4}$ " +  $\frac{3}{4}$ " = 3"
    - The acceptable range is 1½" to 3"



^

### **Placement Time**

- Non-agitated Concrete
  - Place within 30 minutes of adding the cement to the water
- Agitated Concrete
  - Use Table 401-5

TABLE 401-5: AMBIENT AIR TEMPERATURE AND AGITATED CONCRETE PLACEMENT TIME							
T = Ambient Air Temperature at Time of Batching (°F)	Time limit agitated concrete must be placed within, after the addition of cement to water (hours)	Admixtures					
T < 75	1 ½	All Cases					
75 ≤ T < 90	1	None					
75 ≤ T < 90	1 ½	Set Retarder					
T <sub>c</sub> = Concrete Temperature at time of placement (°F)	Time limit agitated concrete must be placed within, after the addition of cement to water (hours)	Admixtures					
90 ≤ T <sub>c</sub> *	3/4	All Cases					
Other conditions contributing to quick stiffening of concrete	3/4	All Cases					



### **Reinforcing Steel**

- Division 700 Structures
  - Section 711 Reinforcing Steel
- 4 Major Questions
  - Is it Clean and Free of heavy rust?
  - Is it properly
    - Tied?
    - · Spaced?
    - Supported?
  - Is there adequate clearance ---
    - From the forms?
    - · Between the mats?
    - From the top of concrete?
  - Is there a defined pattern?



11


### **Reinforcing Steel Storage**





### **Abutment Reinforcing Steel**








13


### **Reinforcing Steel on Steel Bridge**












### **Reinforcing Steel in RCSH**




17

### **Construction Requirements**

- Construction Requirements:
  - Remove heavy mill scale or rust
  - · Check for proper bar spacing
  - Verify the bars are tied adequately
    - · Spacing of ties meet requirements
      - · Tie perimeter steel at all intersections
      - Tie rest of steel intersections at 24 inches or less in all directions
  - Verify the pattern
  - · Check for adequate clearance





### **Epoxy Coated Reinforcing Steel**

- Construction Requirements:
  - Use padded or non-metallic slings
  - Patch <u>ALL</u> cracks or defect in coating
    - · Especially at Ends and Bends
  - Use plastic coated wire ties
  - Protect from UV light
    - · Required to be covered for long term storage
  - Use plastic coated bar chairs



21

### **Table 711-1**

TABLE 711-1: BAR SIZE WEIGHTS					
Bar Size (US Customary)	Bar Size (SI)	Weight (Pounds / Lin.Ft.)			
#3 or 3/8"	9 or 10*	0.376			
#4	12 or 13	0.668			
#5	15 or 16	1.043			
#6	19 or 20	1.502			
#7	22	2.044			
#8	25	2.670			
#9	29 or 30	3.400			
#10	32	4.303			
#11	35 or 36	5.313			
#14	43 or 45	7.650			
#18	55 or 57	13.600			

\*Consult with KDOT's Bureau of Design, State Bridge Office, to determine the correct conversion of the 10mm bars.




### **KDOT Measure and Payment**

- Measure and Payment (Section 711.4)
- Table 711-1 for Weights
- Compute to the nearest 1.0 lb
  - N = number of bars of specific mark (A3, PB2, etc.)
  - L = length of specified bar
  - W = unit weight of bar size in (lb/ft) (Table 711-1)
- Total Mark Weight = N x L x W
  - · Measured to the Nearest Pound
  - Paid to the Nearest Ten Pounds




23

### **Bar Measurement Example 1**



What is the total A7 weight?

- Count the Number of Bars:
  - 7 bars at each wing
  - 2 wings per abutment
  - 2 abutments per bridge
  - 7 x 2 x 2 = 28 bars






24

### **Bar Measurement Example 2**

		BILL OF REINFORCING STEEL Epoxy Coated - Grade 60							
		S	traigh	nt Bar	s		Bent	Bars	
		Mark	Size	Number	Length	Mark	Size	Number	Lengt
		S4	#10	4	50'-6"	R/	#7	24	9'-3"
		S6	#10	60	50'-6"	R2	<b>*</b> 7	4	5′-7"
		S8	#10	52	48'-6"	R3	<b>*</b> 7	220	7'-9'
		59	#10	48	44'-0"	S/	#7	60	11'-3
		S/0	+10	40	36'-3"	S2	#7	52	14'-3
		S/4	+10	24	58′ <del>-</del> 0°	53	*7	52	13'-3
		S7	#9	52	42'-8"	A2	#5	62	3'-11'
		SII	#9	40	33'-0"	R5	<b>*</b> 5	8	6'-6"
	_	S/2	#9	36	21'-6"	R6	<b>*</b> 5	8	10'-8
	Rail	S/5	#9	20	42'-6"	710	- 5	-	70 0
	1	5/6	#9	20	.3.3'-0"	A4	+4	164	9'-4"
		5/7	#9	18	24'-6"	A5	+4	62	6'-2
	eck		_			A7	+4	28	4'-9'
	۵	A/	#8	16	41'-8"	R4	#4	220	3'-2
	1					R7	+4	4	10'-8
	Abutment	RH	#6	24	8'-3"				
	me	RI2	<b>*</b> 6	144	9'-8"	R8	#3	384	4'-4"
	5	T/	#6	97	33'-8"	R9	#3	208	4'-6"
	Ab					RIO	+3	52	4'-6"
		A.3	<b>*</b> 5	20	4/′-8*				
						T3-T18			8
		A6	+4	2	32'-8"				
Φ		S5	#4	2	30'-6"				
₹		S/3	#4	80	9'-3"				
9		T2	+4	82	33′-8*				
Ĭ		SC/	+4	78	6'-6"				
er.s			-		-	-			
Superstructure									

What is the total A7 weight?

- Calculate the Length of a single A7 bar:
  - 1'-4" + 1'-4" + 2'-1" = 4'-9' = 4.75 ft





25

### **Bar Measurement Example 3**


TABLE 711-1: BAR SIZE WEIGHTS					
Bar Size (US Customary)	Bar Size (SI)	Weight (Pounds / Lin.Ft.)			
#3 or 3/8"	9 or 10*	0.376			
#4	12 or 13	0.668			
#5	15 or 16	1.043			
#6	19 or 20	1.502			
#7	22	2.044			
#8	25	2.670			
#9	29 or 30	3.400			
#10	32	4.303			
#11	35 or 36	5.313			
#14	43 or 45	7.650			
#18	55 or 57	13.600			

\*Consult with KDOT's Bureau of Design, State Bridge Office, to determine the correct conversion of the 10mm bars. What is the total A7 weight?

- Find the Unit Weight (lb/ft) of the Bar Size Being Calculated:
  - Bar Size = #4
  - Unit Weight = 0.668 lb/ft
- Total A7 Mark Weight
  - 28 bars x 4.75 ft / bar x 0.668 lb/ft = 88.844 lb
    - Measured Weight = 89 lb
    - · Paid Weight = 90 lb



## CIT Structures Foundations





1

- Types of Foundations
  - Spread Footings
    - Where scour is not a concern and rock with adequate bearing capacity is found near the surface.
  - Pile Footings
    - In many cases pile support footings will be recommended.
  - Drilled Shafts
    - When rock is not found near the surface.



- Construction of Foundations
  - Staking
  - Specifications and Plan Details
  - Excavation
  - Placement of footing materials
  - Measurement and Payment




3

- Staking
  - Section 802 Contractor Construction Staking
    - Control Stakes: Do not perform vertical control using GPS.
    - 802.3 c (2) Bridge. Prior to construction, set project control points and Critical Bridge Element control points for the horizontal and vertical location
    - See Table 802-1 Critical Bridge Elements
    - Independent survey under different surveyor
    - 802.3 c (3) Documentation. Provide and maintain a current copy of all field survey notebooks at the project site at all times.




# 4. Foundations • Staking • Section 802 - Contractor Construction Staking • Section 802 - Contractor Construction Staking Bridge Stakeout Set of 17777 Cit. 68 178 Cyrer Mr.73 | B.M. #22 (62.63) | 75 LL 07 11-07.00 | F.C. 12-11.73 | Cit. 68 178 Cyrer Mr.73 | F.C. 11-17.566 |


# Staking Section 802 - Contractor Construction Staking Off-Set Stakes Excavation will destroy the control point. Be certain they are placing Off- Set stakes outside the excavation limits. Keep these stakes preserved.



7. Foundations - Plan Details — Spread Footing

Output





- Excavation
  - Section 204 Excavation and Backfill for Structures
    - Class I Excavation: is the entire volume of whatever nature, except water, found above the Excavation Boundary Plane, with in the limits specified.
    - Class II Excavation: is the entire volume of whatever nature, including water, found below the Excavation Boundary Plane, with in the limits specified.
    - Class III Excavation: Bridge excavation not classified as Class I or Class II. Class III Excavation is the entire volume of whatever nature encountered including water, within the limits specified.

ansas

Cansas

11

- Excavation
  - Spread Footing
    - Normally, the excavation should be carried to the elevation of the footing shown in the plans. A possible exception would be in the event that a satisfactory foundation in rock can be secured at a higher elevation. Contact the Bureau of Structures and Geotechnical Services.
    - Always compare the material encountered at the footing elevation with that shown on the plans and geology report.

- Excavation
  - Footings
    - Equipment –

       Excavators

       and
       Jackhammers



13

- Excavation
  - Spread Footing
    - If the Engineer determines it is necessary to lower a footing below the elevation shown in the Contract Documents, the additional excavation is paid as follows:






- Excavation
  - Spread Footing
    - 204.4 c. Measurement and Payment
    - Additional excavation up to and including 2 feet below the contract elevation is paid at the contract unit price.
    - Additional excavation from more than 2 feet up to and including 6 feet below the contract elevation is paid at 1½ times the contract unit price.
    - Additional excavation more than 6 feet below the contract elevation is paid as Extra Work, SECTION 104.



15

- Excavation
  - Spread Footing
    - 204.4 c. Measurement and Payment
    - Measure the quantity of CUYD's in each zone.
    - Change Order with new Prices





- Placement of footing materials
  - Spread Footing
    - Section 711 Reinforcing Steel and Section 1601 Steel Bars for Concrete Reinforcement.
    - Section 401 General Concrete, Section 402 Structural Concrete and Section 710 Concrete Structure Construction.



17

- Placement of footing materials
  - Spread Footing
  - Placing Rebar and Concrete



- Measurement and Payment
  - Spread Footing
    - Section 710 Concrete Structure Construction \_ The Engineer will measure the various grades of concrete placed in the structure by the cubic yard. No deductions are made for reinforcing steel and pile heads extending into the concrete.
    - Section 711 Reinforcing Steel \_ The Engineer will measure the reinforcing steel by the pound, based on the theoretical number of pounds shown in the Contract Documents or placed as ordered in writing by the Engineer.




19


### 19. Foundations


• PILE FOOTING











- Excavation
  - Pile Footing
    - Complete the excavation before driving any piling. After driving piling remove loose and displaced material.
    - If necessary, reshape and recompact the bottom of the excavation.
    - Piling placed in groups with concrete caps completing the foundation.



24

- Excavation
  - Pile Footings
    - Pile Footing for Pier
    - Typically, the Engineer shall not have any need to change elevation of the footing.





25

- Excavation
  - Pile Footings
    - Pile Footing for Abutment



- Placement of footing materials
  - Pile Footing
    - Section 704 Piling and Section 1609 Steel Piling and Pile Points.
    - Section 711 Reinforcing Steel and Section 1601 Steel Bars for Concrete Reinforcement.
    - Section 401 General Concrete, Section 402 Structural Concrete and Section 710 Concrete Structure Construction.

27

- Placement of footing materials
  - Pile Footing
  - Certified Material





- Placement of footing materials
  - Pile Footing
  - Allowable Pile Hammer



29

- Placement of footing materials
  - Pile Footing
  - Placing Piling




- Placement of footing materials
  - Pile Footing Concrete Cap
  - Placing Rebar and Concrete





31

- Measurement and Payment
  - Pile Footing
    - Section 704 Piling \_ The Engineer will measure the length of steel pile, steel sheet pile, cast-in-place concrete pile and prestressed concrete pile remaining in the structure, by the linear foot.
    - Section 710 Concrete Structure Construction \_ The Engineer will measure the various grades of concrete placed in the structure by the cubic yard.
    - Section 711 Reinforcing Steel \_ The Engineer will measure the reinforcing steel by the pound, based on the theoretical number of pounds shown in the Contract Documents or placed as ordered in writing by the Engineer.









- Excavation
  - Drilled Shafts
    - Specifications Section 703 Drilled Shafts
    - Drilled shafts are considered where footing conditions require bearing to be carried to a rock formation an the following conditions exist:
    - The footing would have short piles
    - The water table is high
    - A spread footing foundation would be uneconomical
    - Concerns about pile driving i.e. overhead clearance

### Kansas Department of Transportation

37

- Excavation
  - Drilled Shafts
    - Drilled shaft lengths shown in the Contract Documents are an estimate from the top of formation elevations determined from borings.
    - Actual formation elevations encountered at each shaft, may require the actual length of each drilled shaft be adjusted.
    - If the Engineer changes the drilled shaft lengths, the Contractor will be advised (in writing) of the revised bottom of rock socket elevation.

- Excavation
  - Drilled Shafts
    - Equipment –
       Excavators or
       Cranes with
       drill rig
       attachment
    - Auger Bits





39

- Excavation
  - Drilled Shafts
    - Equipment –
       Excavators or
       Cranes with drill
       rig attachment
    - Core Barrels




- Excavation
  - Drilled Shafts
    - Equipment –
       Excavators or
       Cranes with
       drill rig
       attachment
    - Clean Out Buckets



Kansas
Department of Transportation

41

- Excavation
  - Drilled Shafts
    - Oversized for Cased Method





- Excavation
  - Drilled Shafts
    - Limestone excavated from the rock socket





Kansas

43

- Excavation
  - Drilled Shafts
    - Identify if excavation is classified as a Dry Shaft or Wet Shaft
    - Read your Specifications, when you are done reading them, read them again and again.
    - Have a copy of the specifications and plans on site at all times.
    - Have any additional correspondence that may have came from Geology. i.e. investigative core hole results

- Placement of footing materials
  - Drilled Shafts
    - Section 711 Reinforcing Steel and Section 1601 Steel Bars for Concrete Reinforcement.
    - Section 401 General Concrete, Section 402 Structural Concrete and Section 703 Drilled Shafts



45

### 45. Foundations

- Placement of footing materials
  - Drilled Shafts
  - Rebar cage rigged from crane





- Placement of footing materials
  - Drilled Shafts
  - Rebar cage rigged from cranes





47

### 47. Foundations

- Placement of footing materials
  - Drilled Shafts
  - Rebar cage





- Placement of footing materials
  - Drilled Shafts
  - Spacers for clearance



49

### 49. Foundations

- Placement of footing materials
  - Drilled Shafts
  - Sonic Tubes
  - Sonic Test all shafts placed by Wet pour method






- Placement of footing materials
  - Drilled Shafts
  - Concrete
  - Over pump Wet and Dry Pours – Provision 15-07015








- Measurement and Payment
  - Drilled Shaft
    - Section 703 Drilled Shafts \_ The Engineer will measure drilled shafts by the linear foot measured from the bottom of the rock socket to the top of the completed drilled shaft.







Kansas Department of Transportation

**Bridge Construction Manual** 

### **5.3 DRIVEN PILE**

### 5.3.1 General

Driven piles are used as the foundation for almost all abutments in Kansas bridges. Likewise they are used as the foundation for many piers in Kansas bridges. Proper pile driving inspection is critical to a successful bridge project.



### What is a driven pile?

There are two types of driven piles: sheet pile and foundation pile. Sheet piles are long, interlocking, rolled steel plates used in retaining structures, such as walls and cofferdams. Foundation piles are long slender columns designed to be driven into the ground. Foundation piles will be discussed here.

Foundation piles are simply columns, designed to transmit surface loads to low lying soil or bedrock. These loads are transmitted by friction between the pile and ground and by point bearing through the end of the pile. The actual amount of frictional resistance or end bearing is dependent on the particular site conditions.

Foundation piles are made of steel, concrete, or timber. Of these materials, steel H-pile and cast-in-place pipe pile are most commonly used in Kansas. The material and size of pile to be used on a particular project are designated in the plans on the General Notes and Summary of Quantities Sheet.



3

### 3. Pile Driving Video





- Pile Driving Inspection
  - Let's just start from the beginning






5

# 5. Pile Driving

• What are H piles?







- SECTION 704 PILING
  - BID ITEMS
  - Piles (\*) (\*\*)
  - Test Piles (\*) (\*\*)
  - Test Piles (Special) (\*) (\*\*)
  - Cast Steel Pile Points

  - Pre-Drilled Pile Holes

**UNITS** 

Linear Foot

**Linear Foot** 

Linear Foot

Each

**Linear Foot** 

- \*Type: Cast-In-Place Concrete, Prestressed Concrete, Steel or Steel Sheet, Corrugated Metal Sheet +
- \*\*Size
- +Black or Galvanized



• SECTION 704


- PILING

Table 704
1: Pile

Formulas

TABLE 704-1: PILE FORMULAS								
Hammer	Pile Type	Formula						
Gravity	Timber	$P = \frac{2  W  H}{S + 1.0}$						
Gravity	Steel Steel Shell Steel Sheet	$P = \frac{3  W  H}{S + 0.35}  \left(\frac{W}{(W + X)}\right)$						
Air/Steam (Single Acting)	All Types	$P = \frac{2  W  H}{S + 0.1}$						
Air/Steam (Double Acting)	All Types	$P = \frac{2 E}{S + 0.1}$						
Delmag and McKierman-Terry*	All Types	$P = \frac{1.6  W  H}{S + 0.1  \left(\frac{X^{**}}{W}\right)}$						
Link-Belt*	All Types	$P = \frac{1.6 \text{ E}}{\text{S} + 0.1 \left(\frac{\text{X}^{**}}{\text{W}}\right)}$						






• Plan Sheets – Quantity Sheet

_										-		$\rightarrow$					
								SUMN	MARY OF E	BRJÓGE	QU	ANTITIE:	S				
		CLASS III		RETE	REINFORCI	NG STEEL	STRUCTU	JRAL STEEL	WELDED	PIL		PILE			MULTI-LAYER		BRIDG
	LOCATION	EXCAVATION	(GRADE 4.0) (AE)	(GRADE 4.0) (AE)(SA)	(GRADE 60)	(GRADE 60) (EPOXY COATED)	(A709) (GRADE 50W)		STUD SHEA CONNECTO			(STEEL) (HPI4x89)	\	ILE HOLE	POLYMER CONCRETE OVERLAY	PROTECTION (AGGREGATE)	DRAINA SYSTE
L	LOCATION	Cu. Yds.	Cu. Yds.	Cu. Yds.	Lbs.	Lbs.	Lbs.	Lbs.	Each	Lin.	Ft.	Lin.Ft.		Lin. Ft.	Sq. Yds.	Cu. Yds.	Lump :
- [																	
	ABUTMENT NO. I	100	18.6	**		<b>#2.550</b>				15	6					264	
	PIER NO. I	*110	97.6		/5,360					_		192		104			
	PIER NO. 2	*//5	96.6		15,160							184		64			
ш	ABUTMENT NO. 2		16.4	**		<b>#2,110</b>				17	2					229	
ш											$\neg$						
Г	SUBSTRUCTURE	325	229,2		30,520	4,660				36	8	376		168		493	
	SUPERSTRUCTURE			362.8		83,/80	117,999	134,282	2,778		-		$\Box$		9/4		Lump S
													T				
	TOTAL	325	229.2	362.8	30,520	87,840	117,999	134,282	2,778	<b>†</b> 3	68	††376		168	9/4	493	Lump S

<sup>\*</sup>Excavation quantities for pier footings are calculated relative to existing ground.

†This includes 4 @ 49' and 4 @ 43'. ††This includes 8 @ 24' and 8 @ 23'.





<sup>\*\*</sup>Ouantities are included in the superstructure total quantity

- Plan Sheets Pile Designation
  - •HP 12 X 53
  - •"H" pile
  - •12" in width and depth
  - •Weighs 53 lbs. per foot



13

# | CONTRACTOR SECURITION | CONT

### 14. Pile Driving - Plan Sheets - Engineering


### PILING:


Drive all piling to penetrate the Lane Shale Member and bear upon the Raytown Limestone Member. Overdriving of pile on hard bedrock will result in damage to the pile. Piles damaged by overdriving must be removed and replaced. Driving shall stop when in the opinion of the Engineer additional driving may damage the piling. Final pile tip elevations should be determined in the field based on force calculations. Drive all piling to the Pile Driving Formula Load of:


Abutments 108 tons Piers 180 tons


As a minimum drive each pile to the load and penetration, but in no case shall the pile be driven to MORE THAN 110% of Pile Driving Formula Driving Load. At any location where problems are experienced, pile damage is suspected, or the Pile Driving Formula Load occurs significantly above the design pile tip elevation, the Engineer may request that the Pile Driving Analyzer (PDA) equipment be used.




















- From the Contractor – Hammer Specs
- Delmag


		_	through D20		1	1	
Models	D6-32	D8-22	D12-42	D16-32	D19-42	D25-32/33	D30-32/3
Maximum Batter		_		_			
standard/extended	1:3	12	1:5/11	1:5/1:1	15/11	1:5/1:1	1:5/1:1
Piston Weight	-					_	
(lbs)	1.322	1,762	2,820	3,528	4.015	5,513	6.615
Energy per Blow (adj)							
max (ft lbs)	13,500	20,100	33,990	40,200	43,225	66,380	75,452
min (ft lbs)	6,300	9.434	15,660	18,871	20.540	29,486	35,383
Bearing Capacity*							
(tons)	68	90	157	201	216	332	377
Blows per Minute							
min/max	38/52	36/52	35/52	36/52	35/52	35/52	36/52
Consumption						'	
Diesel fuel (gal/hr)	0.7	1	0.95	1.45	145	211	2.64
Lubrication oil (gal/hr)	0.16	0.26	0.26	0.26	0.26	0.26	0.26
Capacity					•		
Diesel fuel (gal)	5	5.28	6.34	20	20	17.7	17.7
Lubrication oil (gal)	13	158	1.72	5	5	5.02	5.02
Operating Weights (aprox.)				-		-	
Hammer only (lbs)	5,440	5,870	7,600	8,900	9,500	14,100	15,200
Hammer w/ typical	6,640	7,070	8,800	10,100	10.700	16,100	17,200
drive cap (lbs)							
Anvil (impact block)	370	370	620	753	753	1,360	1,360
Dimensions (in)							
Overall length	196	231	233	233	233	256	256
Hammer length	150	185	186	186	186	207	207
Hammer len. w/ ext.				219	219	246	246
Hammer depth-rear	14	14	14	14	14	19	19
Hammer depth-front	14	14	14	14	14	18	18
Guiding						'	'
Standard (box leads)	8° x 21°	8° x 21°	8" x 21"	8° x 21°	8° x 21°	8° x 27°	8° x 27°
Optional	12"/14" spud	12"/14" spud	8° x 27°	8° x 27°	8° x 27°	8° x 32°	8° x 32°
		1	12'/14'	12°/14°	12"/14"	14" spud	14" spud



23

## 23. Pile Driving

- From the Contractor – Pile and Driving Equipment Data
- DOT Form 217aa






# 24.Pile Driving • From the

- From the Contractor – Pile and Driving Equipment Data
- DOT Form 217aa

	Pile Type			
PILE	Length (in leads)			(ft
	Weight (perfoot)			(Ib
	Wall Thickness	(in)	Taper	
	Cross Sectional Area		_ (in²)	
	Design Pile Capacity		(ton)	
	Description of Splice			
	Tip Treatment Description			
NOTE: If a mandrel.	or follower, is used to drive the pile, attac	h the manufac	turer's detail sh	eets includir
the weight an	d dimensions.			
the weight an	d dimensions.	Date		
the weight an		Date		
the weight an Submitted by  One Copy Each Sent To:		Date		
Submitted by  One Copy Each Sent To:  Bureau of Construct Bureau of Design, S	tion and Maintenance tate Bridge Office	Date		
the weight an Submitted by  One Copy Each Sent To:  Bureau of Construct  Bureau of Design, S  Bureau of Materials	tion and Maintenance	Date		
Submitted by  One Copy Each Sent To:  Bureau of Construct Bureau of Design, S	tion and Maintenance tate Bridge Office	Date		





- What have we done so far?
  - Read the specifications.
  - Familiarized ourselves with the plans.
  - Know quantity, lengths and bearing capacity.
  - Know orientation and placement within the foundation.
  - Began setting up final documentations.
  - Began setting up field notes for actual pile driving.



27

## 27. Pile Driving

- What have we done so far?
  - Know our Ordered and Accepted Lengths.
  - Know the Pile dimension and weight.
  - Know the Pile hammer to be used.
  - Know our Pile driving formula.







- Driving Pile
  - Check for correct Piling used
  - Check heat number
  - Pile Points if specified





31

## 31.Pile Driving

- Driving Pile
  - Determine placement
  - Check Axis
  - Check spacing





- Driving Pile
  - Check for Plumb
  - Set Pile





33

## 33.Pile Driving

- Driving Pile
  - Leads and Hammer
  - Ram (striking part)
  - Anvil
  - Cap
  - Pile

Once pile driving begins it is a very quick and fluid motion





- Driving Pile
  - Mark distance of penetration
  - Count blows





35


### 35.Pile Drivir

- Driving Pile
  - Measure distance of penetration in 20 blows
  - Average





- Driving Pile
  - Check height of drop
  - Compensate for the distance through the hammer
  - Mark hammer and leads 1' increments





37

### 37. Pile Driving

• We know our Pile formula, right?

TABLE 704-1: PILE FORMULAS									
Hammer	Pile Type	Formula							
Gravity	Timber	$P = \frac{2  W  H}{S + 1.0}$							
Gravity	Steel Steel Shell Steel Sheet	$P = \frac{3  W  H}{S + 0.35}  \left(\frac{W}{(W + X)}\right)$							
Air/Steam (Single Acting)	All Types	$P = \frac{2  W  H}{S + 0.1}$							
Air/Steam (Double Acting)	All Types	$P = \frac{2 - E}{S + 0.1}$							
Delmag and McKierman-Terry*	All Types	$P = \frac{1.6  W  H}{S + 0.1  \left(\frac{X^{**}}{W}\right)}$							
Link-Belt*	All Types	$P = \frac{1.6 \text{ E}}{\text{S} + 0.1 \left(\frac{X^{**}}{\text{W}}\right)}$							



<sup>\*</sup>diesel hammers

\*\* For diesel hammers, the quantity X/W shall not be less than 1.

P = safe bearing power in pounds

W = weight in pounds, of striking part of hammer

H = height of fall in feet

E = energy of ram in foot-pounds per blow

S = the average penetration in inches per blow for the last 5 blows for gravity hammers and the last 20 blows for air/steam or diesel hammers

X = weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving

• Delmag Diesel Hammer Pile Formula

$$P = 1.6 W H$$
  
S+ 0.1 (X/W\*\*)



39

### 39. Pile Driving

- P= safe bearing power in pounds
- W= weight in pound, of striking part of hammer
- H= height of fall in feet
- S= the average penetration in inches per blow for the last 20 blows for diesel hammers
- X= weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving



- P= safe bearing power in pounds
- W= 4,190 lbs. (striking part of hammer)
- H= 10 feet (height of hammer drop)
- S= 0.15 (3 inches /20 blows)
- X= 4550 lbs. (2597 lbs. pile (49'x53) + 1953 lbs. cap and/or anvil)



41

41. Pile Driving – Delmag Diesel Hammer Pile Formula

W = weight (lbs) of striking part of Hammer

H = height of hammer drop (ft)

P = 1.6 \* 4190 \* 10

0,15+0.1(4550/4190\*\*)

S = Average penetration in inches per blow for the last 20 blows

X = weight (lbs) of the pile plus the weight of cap and anvil



• Delmag Diesel Hammer Pile Formula

$$P = \frac{67040}{0.15 + 0.1(4550/4190**)}$$



43

### 43. Pile Driving

• Delmag Diesel Hammer Pile Formula

$$P = \frac{67040}{0.15 + 0.1(1.09**)}$$

\*\* Diesel quantity x/w shall not be < 1



• Delmag Diesel Hammer Pile Formula



45

### 45.Pile Driving

• Delmag Delmag Diesel Hammer Pile Formula



• Delmag Diesel Hammer Pile Formula

$$P = 258,842 lbs.$$



47

### 47. Pile Driving

• Delmag Diesel Hammer Pile Formula



• Delmag Diesel Hammer Pile Formula

P = 129 tons
Plans called out 108 tons
Don't drive over 110%



49

### 49. Pile Driving


- Driving Pile
  - Over driven pile
  - OUCH...!





- Diesel Hammer Pile Formula
  - Back figure and solve for "S" prior to driving the pile. Have these notes with you as the pile driving is being performed.
  - The actual driving of the pile goes rather quickly; you need to be prepared with instructions to the contractor and inform him that satisfactory bearing has been achieved.
  - If you feel there is a problem, contact Geology.





- 2nd example Delmag Diesel Hammer 40' (shorter pile)
- P= safe bearing power in pounds
- W= 4,190 lbs. (striking part of hammer)
- H= 10 feet (height of hammer drop)
- S= 0.15 (3 inches /20 blows)
- X= 4073 lbs. (2120 lbs. pile (40'\*53) + 1953 lbs. cap and/or anvil)



53

### 53. Pile Driving

• Diesel Hammer Pile Formula

$$P = \frac{1.6 * 4190 * 10}{0.15 + 0.1(4073/4190**)}$$



• Diesel Hammer Pile Formula

$$P = \frac{67040}{0.15 + 0.1(4073/4190**)}$$



55

### 55. Pile Driving

• Diesel Hammer Pile Formula

$$P = \frac{67040}{0.15 + 0.1(0.97**)}$$

\*\* Diesel quantity x/w shall not be < 1



• Diesel Hammer Pile Formula

$$P = \frac{67040}{0.15 + 0.1(1.00)}$$

\*\* Diesel quantity x/w shall not be < 1



57

### 57.Pile Driving

• Diesel Hammer Pile Formula



• Diesel Hammer Pile Formula



59

### 59. Pile Driving

• Diesel Hammer Pile Formula



- 704.4 c. Driving Piles
- Completed pile driving – ....
  - Check position of pile






61

### 61. Pile Driving

- 704.4 c. Driving Piles
- Do not force misaligned piles into proper position.
- If the pile is 35 feet or less in length, the maximum allowable variation from the vertical or battered lines ¼ inch per foot of length.
- If the pile is greater than 35 feet in length, the maximum allowable variation from the vertical or battered lines 1/2 inch per foot of length.
- The maximum allowable variation on the head of the driven pile from the position - 2 inches for piles used in bents, and 6 inches for foundation piles.



- 704.4 c. Driving Piles
- Drive all piles in the orientation shown on the Plans. If the axial orientation of the pile rotates or twists by more than 10°,






63

# 63. Pile Driving

 the Field Engineer will contact the Bureau of Structures and Geotechnical Services.





- Pile elevation after driving to determine pay pile and cut-off.
- Pile Cut-Off
- Pile remaining in structure





65

# 65. Pile Driving

- 704.5 MEASUREMENT AND PAYMENT
  - The Engineer will measure the length of steel pile, steel sheet pile, cast-in-place concrete pile and prestressed concrete pile remaining in the structure, by the linear foot.
  - The Engineer will measure each cast steel pile point used.



- 704.5 MEASUREMENT AND PAYMENT
  - If after driving the ordered and accepted length of pile, plan bearing is not achieved and additional pile is required, the Engineer will measure for payment each pile splice needed to lengthen the pile to achieve bearing.



67

## 67. Pile Driving

- 704.5 MEASUREMENT AND PAYMENT
  - The Engineer will measure pile cut-off by the linear foot for Pile (\*) (\*\*). Pile cut-off is the difference between the length of pile ordered and accepted and the actual length of pile remaining in the structure.
  - Payment for pile splices at 4 times the contract unit price of the type of pile spliced is full compensation for the specified work.



• 704.5 MEASUREMENT AND PAYMENT

TABLE 704-2: PIL	E CUT-OFF PAYMENT
Pile Type	% of Contract Unit Price Paid
Cast-in-place (Shell)	60
Pre-stressed concrete	75
Steel	75
Steel Sheet	75



69

# 69. Pile Driving


- 704.5 MEASUREMENT AND PAYMENT
  - Steel Pile \_ Unit price \$55.00 Inft
  - Table 704-2 \_ 75% of unit price
  - \$55.00 \* 75% = \$41.25
  - Inft cut-off determined by DOT Form 217 = 12.35'
  - Amount added to contract = \$509.44







# 708- Falsework & 710 -Form Construction

F&F-1





	Plan Review Summary Information										
	Inf Plan Type	ormation	# of Plan Copies	Lead Time Required	Specs to Review	Note	Review	P.E. Stamp Required	Plan Review	Recommend Approval	
		Consultant	*	Project Specific	101 106 705 707 709 716	5200 6000 6010 6100	6200 6210 6220 6410	No	No	**	
	Shop Details	In House	*	Project Specific	719 721 722 735 1609	6110 6111 6115 6120 6130	6420 6600 6620 6625 7410	No	Yes	**	
	Shoring	Standard Railroad	*	3 weeks 6 weeks	701 702	30 35 300 1030		Yes	Yes	Yes	
Timeline for Submittals	Falsework	Category (1)	*	4 weeks	105 708 710	4100 4105 4115 4120 4100	4130 4140 7800 7810 4130	Yes	Yes	Yes	
Submittals:	L	Category (2)	*	4 weeks	105 708 710	4106 4110 4120	4140 7800 7820	Yes	Distric	t Policy	
		Category A	(1)		105 708	3000 3010	6521	No	No	No	
(Covered in S. Spec	Erection	Category B	*	4 weeks	710 SP07-	5210 6420	6522 6523 8700	Yes	Yes	Yes	
(Covered in S. Spec. 105.10 Plans & Working		Category C	*	4 weeks	07004		520	Yes	Yes	Yes	
		Category A	(1)		105 708	3000 6521 3010 8700	6521 8700	No	No	No	
Drawings) <i>(p. 100-43)</i>	Demolition	Category B	*	4 weeks	710 SP07-	5210 6420	9001 9002	No	No	No	
		Category C	*	4 weeks	07014	6520	9003	Yes	Yes	Yes	
	Pour Sequence	Discuss Possible Changes at Precon Meeting	*	2 Weeks	105 708 SP07- 0711	4140 4200 5100 5110 7000 7210 7215	7300 7301 7310 7311 7312 7320 7330 7400	No	Yes	Yes	
	Based on project comp of what is required. * Electronic submittal of Construction * * General Complian	onforming to 10									Kansas Department of Transportation



Based on project complexity, the specifications and the notes listed in this document may only be the base of what is required.

- \* Electronic submittal conforming to 105.10 (b) of the Standard Sepcifications for State Road and Bridge Construction
- \* \* General Compliance Stamp



5

# 105.10 b. Plans & Working Drawings:

#### 105.10 PLANS AND WORKING DRAWINGS

a. Plans. The Secretary may provide plans showing lines, grades, roadway typical cross-sections, all structures, and a summary of contract pay items. Steel bridge plans show only general features. Keep one set of plans on the Project site.

b. Working Drawings. Submit an electronic copy of working drawings in Adobe PDF (Portable Document Format) file format, with a maximum internal page size of 17 inches by 11 inches. For each deliverable (falsework plans for a structure, shop drawings for structural elements which will be fabricated, etc.), submit the copy in one transmission, with the sheets consecutively numbered, and with no duplications of sheets.

- c. Timely Submittal. Provide all working drawings to the Field Engineer or designated KDOT office at the time the Progress Schedule/Network Schedule identifies or at a date that allows the reviewing Engineers at least 15 business days to review the drawings. If the Contractor desires the drawings be reviewed in less than 15 business days, notify the Field Engineer or designated KDOT office that the time for review and approval is critical. While KDOT will attempt to accommodate the Contractor's time frame, KDOT makes no guarantee that KDOT will complete the review process in less than 15 business days.
- d. Timely Review. Within 15 business days after the Contractor has provided initial or revised working drawings to the Field Engineer or designated KDOT office, the Field Engineer or designated KDOT office will review and either approve or reject the drawings. If rejected, correct and resubmit revised working drawings for the Engineer's approval. Allow the Field Engineer and other reviewing Engineers a reasonable time for subsequent review and approval. The Contractor assumes all risk of delay incurred for revisions and the Engineer's review of these revisions. If KDOT fails to accept or reject initial or revised drawings within 15 business days, the Contractor may seek compensation under subsection 104.6 for additional time or acceleration costs.
- e. Responsibility for Working Drawings. The Contractor has sole responsibility for the adequacy and accuracy of the working drawings. The Engineer's approval of the working drawings is for KDOT's benefit, not to ensure Contractor quality control. The Engineer's review and/or approval are not intended as an undertaking of the Contractor's duty to provide adequate and accurate working drawings.

(p. 100-43)



### Falsework vs. Formwork

### Falsework:

- Temporary Construction used to support vertical loads during construction
- "Works" to hold the structure up

#### Formwork:

- Temporary Structure to mold concrete into desired shape until hardened
- "Forms" the concrete



7

# 708.3 a. Falsework Design:

(p. 700-35)

- Contractor is responsible for Falsework Design Plans by a licensed P.E.
- Field Engineer submits Falsework
   Plans to Bridge (or Local Projects if structure is on City or County System)
- Bridge/Local P. will review Falsework
   Drawings and remit to Field Engineer



# 708.3 a. Design Requirements:

#### a. Falsework Design.

(1) General Falsework Design Requirements. Design falsework according to the KDOT Bridge Design Manual, Falsework Design, Analysis and Inspection.

Include the type, size, grade and finish of all lumber used. Provide adequate details of the proposed method of construction. The Engineer may request additional information.

In designing forms and centering, regard concrete as a liquid. In computing loads, assume a weight of 150 (p.700-35) pounds per cubic foot for the vertical pressure, and a minimum of 85 pounds per cubic foot in computing horizontal

Do not place cast-in-place shear bolts, coil inserts or other devices used as falsework support in pier columns without the approval of the Engineer. Through bolts are permitted. Do not drill and grout bolts or other devices into

(2) Category 1 Structures. On the structures listed below, submit to the Engineer for review (See SECTION 105) by the State Bridge Office (SBO) (or Bureau of Local Projects) and, if applicable, the railroad company, 7 copies of detailed falsework plans designed and sealed by a Professional Engineer

- All structures over or under railroad tracks;
- All structures built over highways or streets carrying traffic;

  All structures requires 5 to a street structures requires 5 to a street structure requires 5 to a st All structures requiring falsework that directly carries highway traffic loads during construction;
- Deck overhangs greater than beam depth or greater than 54 inches;
- Superstructure forming with "non-typical" support (i.e. needlebeams); and
- All structures that require falsework plans to be submitted to the SBO (or Bureau of Local Projects) as noted in the Contract Documents.

(3) Category 2 Structures. If not included in the Category 1 structures above, submit to the Engineer for review (See SECTION 105) by the Field Engineer, 3 copies of detailed falsework plans designed and sealed by a Professional Engineer on the Category 2 structures listed below. (Cat 2: Field Engineer or District E.)

• All cast-in-place span structures supported on falsework:

- Concrete Box Structures with cell spans greater than 16 feet or cell heights greater than 14 feet;
- Decks with girder spacing equal to or greater than 14 feet; and
- Substructure forming with "non-typical" support.



9

# 708.3 a. Design Requirements:

- (p.700-35)When computing loads, concrete is treated as a liquid.
- No cast-in-place shear bolts, coils, or other devices to support falsework in piers
- Through-bolts are permitted
- Do not drill and grout bolts or other devices unless stated in contract documents
- Know the difference between Category 1 and Category 2 Structures (pg. 700-35)



# Construction Requirements: Section 708.3 b. (p. 700-36)

b. Falsework Construction. Adhere to all falsework details.

Drive falsework piling to a satisfactory depth and bearing value to support all falsework that is not founded on rock, shale or thick deposits of other compact material in their natural beds. Do not use mudsills on earth, sand, gravel and similar materials, unless otherwise noted in the Contract Documents. Do not support falsework on any part of the structure, except the footings, without written approval from the Engineer. The number and spacing of falsework piling, the adequacy of sills, caps and stringers, and the amount of bracing in the falsework framing is subject to approval of the Engineer.

If the falsework piling or vertical members are of sufficient length to cap at the desired elevation for the horizontal members, cap them and construct frames to the proper elevation. If falsework piling are not of sufficient length, extend them using an approved pile splice. Do not use wedges at pile splices. Cut the ends of the piling or vertical members square for full bearing. If vertical splices are necessary, the abutting members shall be of the same approximate size, with the ends cut square for full bearing. Provide an adequate splice to maintain rigidity of the joint, including inserting a #9 reinforcing bar 18 inches into each end of the abutting members.

Upon completion, remove all forms and falsework according to SECTION 710. Pull or cut off falsework piling 12 inches below low water level, the natural ground or the bottom of a channel change. On grade separation structures, pull or cut off the falsework piling 12 inches below subgrade elevation of the roadbed that the piles are driven into. Pull or cut off all other falsework piling 12 inches below finished grade.

Unless the Contract Documents provide for permanent camber, construct the falsework to provide only sufficient camber to prevent final settlement below the finish grades shown in the Contract Documents. Use adequate hardwood wedges or screw jacks in all falsework construction, and place and adjust them to provide the proper form alignment. If required, provide a means for adjusting forms to offset any excessive settlement. When screw jacks are used, adequately brace and secure them to prevent tipping of the jacks in any direction.



11

## 708.3 b. Falsework Construction

(p. 700-36)

- Pile splicing should be avoided
- When approved, spliced pieces should be nearly the same diameter, ends squared, and the joint should be braced and banded. (See Bridge Construction Manual for Example)
- Provide some means for measuring
   Settlement during concrete placement







13

# Falsework Inspection Requirements: Section 708.3 c. (p. 700-36)

c. Falsework Inspection Requirements. For Category 1 structures, the falsework designer of record shall make a Falsework Inspection of the as-built falsework for substantial compliance with the falsework plans prior to placing concrete in the structure.

Conduct an on-site review of the falsework. Items to be reviewed include but are not limited to:

- The condition of the materials used for piling, cross bracing, beams, plywood decking, shims and jacks.
- The size and spacing of all structural members regarding their compliance to the submitted falsework plan.
- The condition and compliance of all splices.

Provide written documentation to the Engineer stating the falsework as-built is acceptable and in compliance with the original sealed plans. If the falsework is not in compliance, make corrections to the falsework or submit a revised, sealed falsework design prior to the placement of any concrete. When modifications are made to the falsework, the designer of record shall make Falsework Inspections until written documentation is provided to the Engineer stating that the falsework is in compliance, at no additional cost to KDOT.

For Category 2 falsework plans, conduct a walk-though review of the falsework with the Field Engineer, prior to placing concrete in the structure. Variations and deficiencies from the plan will be noted in writing and supported with photos or sketches. Forward the documentation to the falsework designer. The designer must respond in writing that the deficiencies are minor and the falsework is in substantial compliance, or must propose a new falsework plan which addresses the deficiencies.

The Engineer will refuse approval to proceed with other phases of the work if the falsework is determined to be unsafe or inadequate to properly support the subjected loads.



### Falsework Inspection Requirements: Section 708.3 c. (p. 700-36)

### Category 1

- Check condition of all materials used in Falsework
- Check the size and spacing of all members are in compliance with Falsework Plans
- The condition and compliance of all splices
- Provide written documentation of Falsework as-built approval

### Category 2


 Conduct a walk-through review with the Field Engineer <u>before</u> placing concrete























# Deck Overhangs:


FALSEWORK Plans required if:


Overhang > Depth

-or-

Overhang > 54 inches









(NEVER Weld Hangers)







27



# Formwork:

708.3 d. (p. 700-36)



# Formwork:


- Wood/plywood shall be sound & installed with grain running in the same direction
- Mortar-tight, with no warping or bulging
- No permanent aluminum deck forms
- Oil formed surfaces with clear, paraffin based oil
- Moisten wood forms with water before placement
- Bevel all exposed edges with ¾" triangular molding








29



What are Fillets and why are they used?






Fillets: Conc. placed over top flange to adjust for beam deflection due to Dead loads.

Should always be positive. (Typically 1" to 3".)

Will be smallest over Piers.

Typ. Deflection Diagram:





31

# Removal of Forms: 710-Conc. Construction, p. 700-40







# Removal of Forms: 710-Conc. Construction

**CURING:** Figure 710-1 (p. 700-42)

**■ CURE TIMES:** Table 710-1 (p. 700-45)

■ LOAD LIMITS: Table 710-2 (p. 700-46)

■ *REMOVAL OF FORMS:* Table 710-3 (p. 700-48)





# **Removal of Forms:**

TABLE 710-3: MINIMUM STRI FALSEWORK (I		JAIN III	AE BEFOR	E KEMO	JVAL O.	FFORMS	æ					
	Span Length (feet)											
Type of Work	Less than 10	10 or less	Greater than 10	10 to 20	20 + to 30	Greater than 20	Greater than 30					
Cantilevered Piers - Formwork (supporting the pier beam) supported on column		7 <sup>∆</sup> [4]*	10 <sup>∆</sup> [6]*									
Column Bent Piers - Falsework supporting pier beam**	4 △			7 <sup>∆</sup> [4]*		10 <sup>∆</sup> [6]*						
Forms and Falsework under slabs, beams, girders, arches and brackets***	4 <sup>Δ</sup>			7 <sup>∆</sup> [4] <sup>†</sup>	10 <sup>Δ</sup> [6] <sup>+</sup>		15 <sup>Δ</sup> [10] <sup>+</sup>					
RCB and RFB top slabs not re-shored		7 <sup>∆</sup> [4] <sup>†</sup>		7 <sup>∆</sup> [4] <sup>+</sup>		10 <sup>Δ</sup> [6] <sup>†</sup>						
Т	Tim	Time (Days)										
Walls, Wing Walls and vertical sides of Do not backfill according to SECTION	4	4 <sup>Δ</sup> [3]*										
Footing Supported on Piles - minimum columns	or 2	4 <sup>Δ</sup> [2]*										
Spread Footing founded in rock – minin columns	num befo	re erecting	g forms and	reinforci	ng steel f	or	2 <sup>Δ</sup>					
Footing supported on piles - minimum columns	cure befo	re erecting	forms and	reinforci	ng steel f	or 4	<sup>∆</sup> [2]*					
Columns for cantilevered piers - 1. minimum before supporting form	he 4	4 <sup>Δ</sup> [2] <sup>+</sup>										
column.  2. minimum before placing concrete f	7	<sup>∆</sup> [4] <sup>+</sup>										
Columns for bent piers -  1. minimum before erecting formwork 2. minimum before placing concrete f		2 <sup>Δ</sup> 4 <sup>Δ</sup> [2]*										
Drilled shafts - minimum before erecting		2 <sup>Δ</sup>										
Floors for RCB and RFB structures on r - minimum before erecting forms and re		2 △										
Floors for RCB and RFB structures on s - minimum before erecting forms and re	oil or fou inforcing	ndation sta steel					<sup>∆</sup> [2]*					
Do not remove forms or falsework fr tensioning forces are transferred.	ost	NA										

**Table 710-3** (p. 700-48)

 $\Delta$  - increase the time period 3 days when supplemental cementitious materials are used Oct 1 – April 30

\* , \*\*, \*\*\* or + - refer to Note below Table





	TABLE 710-3: MINIMUM STRENGTH GAIN TIME BEFORE REMOVAL OF FOR FALSEWORK (DAYS)							
	THESE WORK (	JA15)		Span	Length (	feet)		
(Type) Structural Element:	Type of Work	Less than 10	10 or less	Greater than 10	10 to 20	20 + to 30	Greater than 20	Greater than 30
(P.B. Formwork) on Single Col.:	Cantilevered Piers - Formwork (supporting the pier beam) supported on column		7 <sup>∆</sup> [4]*	10 <sup>∆</sup> [6]*				
(P.B. Falsework) on Multiple Col.'	Column Bent Piers - Falsework supporting pier beam**	4∆			7 <sup>∆</sup> [4]*		10 <sup>Δ</sup> [6]*	
(Forms/Falsework) for Decks:	Forms and Falsework under slabs, beams, girders, arches and brackets***	4 <sup>Δ</sup>			7 <sup>∆</sup> [4] <sup>†</sup>	10 <sup>Δ</sup> [6] <sup>†</sup>		15 <sup>∆</sup> [10] <sup>†</sup>
Box Culverts Roofs:	RCB and RFB top slabs not re-shored		7 <sup>∆</sup> [4] <sup>+</sup>		7 <sup>∆</sup> [4] <sup>+</sup>		10 <sup>Δ</sup> [6] <sup>+</sup>	
	T	ype of W	ork				Time	(Days)
Box Culvert Walls & Wings:	Walls, Wing Walls and vertical sides of RCB and RFB structures  Do not backfill according to SECTION 204, until 3 days after forms are removed.  4 <sup>4</sup> [3]*							
(Col. Forms) on Pile Cap Footings:	Fratis Company de de Dila minimum la firm de							
(Col. Forms) on Spread Footings:	Spread Footing founded in rock – minin columns							2 ⁴
(Duplicate, ignore:)	Footing supported on piles - minimum columns	cure befo	re erecting	g forms and	reinforci	ng steel fo	or 4.4	[2]*
(P.B. Forms), 1- Column:	Columns for cantilevered piers -  1. minimum before supporting form column.			steel for th	e pier be	am on th		2[2]+
	minimum before placing concrete for Columns for bent piers -	or the pier	r beam				74	<sup>1</sup> [4] <sup>+</sup>
(P.B. Forms), Multiple Columns:	minimum before erecting formwork     minimum before placing concrete fi			el for the pi	er beam			2 <sup>Δ</sup> (2]*
(Col. Forms) Drilled Shafts:	Drilled shafts - minimum before erecting				the colur	nns		2 <sup>Δ</sup>
Box Culverts Floors on Rock:	Floors for RCB and RFB structures on r - minimum before erecting forms and re	inforcing	steel					2 ∆
Box Culverts Floors on Soil:	Floors for RCB and RFB structures on s - minimum before erecting forms and re	inforcing	steel					(2]*
	Do not remove forms or falsework fr tensioning forces are transferred.	om post	tensioned	elements u	ntil all a	ppned pos	1	NA De


- \* Contractors may reduce the time required before form removal to the number of days shown in brackets, provided the concrete is shown to have attained a minimum strength of 65% of the specified f 'c. To accomplish this, prepare the necessary cylinders, obtain the services of an approved laboratory to break them at the appropriate time and provide a report to the Engineer. Field cure the cylinders alongside and under the same curing conditions, as the concrete they represent.
- \*\* Do not set girders or beams on the pier beams until the falsework under the pier beams is removed.
- \*\*\* Remove the formwork from subdecks or one-course decks within 6 weeks after the deck has been placed.
- \* Contractors may reduce the time required before form removal to the number of days shown in brackets, provided the concrete is shown to have attained a minimum strength of 75% of the specified f'c. To accomplish this, prepare the necessary cylinders, obtain the services of an approved laboratory to break them at the appropriate time and provide a report to the Engineer. Field cure the cylinders alongside and under the same curing conditions, as the concrete they represent.
- <sup>a</sup> Increase the time period 3 days when supplemental cementitious materials are used October 1 thru April 30.
  - \* reduce by days if attain 65% f'c
  - \*\* Do Not set beams on pier beam until falsework under pier beam is struck
  - \*\*\* remove formwork within 6 weeks of placement
  - + reduce days if attain 75% of f'c


 $\Delta$  - increase the time period 3 days when supplemental cementitious materials are used Oct 1 – April 30











41


# **Example Questions**

Q1: Concrete columns for a 3-column bent pier were poured yesterday. How long from concrete placement can pier beam formwork erection start?

- 1. Structural Element? 3-Column Bent
- 2. Type of Work?

  Pier Beam Formwork






# Example Questions:

Q2: How long from initial (3 column) pour before placing concrete for the pier beam?

- 1. Structural Element?
- 3-Column Bent
- 2. Type of Work?

  Pier Beam Concrete placement






Q3: The concrete deck for a steel girder bridge was placed on October 15th. The width of the deck is 60'. There are 6 girders spaced at 9'-0". No test specimens were made. How many days between the deck placement and when the deck forms can be removed?

1. Structural Element?

Deck, girders spaced at 9 Ft.

2. Type of Work? removal of Deck Forms





# **Example Questions:**


Q4: The concrete deck for a steel girder bridge was placed on October 15th. The width of the deck is 60'. There are 6 girders spaced at 9'-0". No test specimens were made. Supplemental cementitious materials were added. How many days between the deck placement and when the deck forms can be removed?


- 1. Structural Element?

  Deck, girders spaced at 9 Ft

  with S.C.M.'s,  $\Delta = \text{add 3 Days}$
- 2. Type of Work? removal of Deck Forms








Q5: The concrete deck for a prestressed concrete beam bridge was placed yesterday. The width of the deck is 60'. There are 5 girders spaced at 11'-0".

No test specimens were made. How many days between the deck placement and when the deck forms can be removed?

- 1. Structural Element?

  Deck, girders spaced at 11 Ft.
- 2. Type of Work? removal of Deck Forms





# **Example Questions:**

Q6: How many days if grade 4.0 concrete (4000 psi) is specified, and test specimens broke at a strength of 3100 psi after 4 days?

1. Structural Element?

Deck, girders spaced at 11 Ft.

+ Cylinders made, broke on Day 4

Requirement for: + = reduce days if attain 75% of f'c

0.75(4000) = 3000 psi Needed


break of 3100 > 3000 req'd, OK.

Remove forms on Day 4 after breaks.

2. Type of Work? removal of Deck Forms



	TABLE 710-3: MINIMUM STRENGTH GAIN TIME BEFORE REMOVAL OF FORMS & FALSEWORK (DAYS)									
1. Structural Element?	,		Span Length (feet)							
Deck, 11 Ft. span	Type of Work	Less than 10	10 or less	Greater than 10	10 to 20	20 + to 30	Greater than 20	Greater than 30		
Беск, 11 1 г. зрин	Cantilevered Piers - Formwork (supporting the pier beam) supported on column		7 <sup>∆</sup> [4]*	10 <sup>∆</sup> [6]*						
	Column Bent Piers - Falsework supporting pier beam**	4∆			7 <sup>∆</sup> [4]*		10 <sup>Δ</sup> [6]*			
2. Type of Work?	Forms and Falsework under slabs, beams, girders, arches and brackets***	4 <sup>∆</sup>			7 <sup>∆</sup> [4] <sup>†</sup>	10 <sup>Δ</sup> [6] <sup>†</sup>		15 <sup>∆</sup> [10] <sup>+</sup>		
Removal of	RCB and RFB top slabs not re-shored		7 <sup>∆</sup> [4] <sup>+</sup>		7 <sup>∆</sup> [4] <sup>†</sup>		10 <sup>Δ</sup> [6] <sup>+</sup>			
E	Type of Work						Tim	e (Days)		
Forms —	Walls, Wing Walls and vertical sides of RCB and RFB structures  Do not backfill according to SECTION 204, until 3 days after forms are removed.							4 <sup>Δ</sup> [3]*		
- [4] Dava	Footing Supported on Piles - minimum cure before erecting forms and reinforcing steel for columns						4	4 <sup>∆</sup> [2]*		
$= [4] Days \longleftrightarrow$	Spread Footing founded in rock – minimum before erecting forms and reinforcing steel for columns									
+ cylinders made	Footing supported on piles - minimum cure before erecting forms and reinforcing steel for columns						or 4	<sup>∆</sup> [2]*		
roke above Req'd .?	Columns for cantilevered piers - 1. minimum before supporting forms and reinforcing steel for the pier beam on the column									
	2. minimum before placing concrete f	or the pier	beam				7	Δ [4] <sup>+</sup>		
Yes. = Remove at 4	Columns for bent piers - 1. minimum before erecting formworl 2. minimum before placing concrete f			el for the pi	er beam			2 <sup>Δ</sup> <sup>Δ</sup> [2]*		
Days.	Drilled shafts - minimum before erectin	g forms ar	nd reinford	ing steel for	r the colur	nns		2 <sup>Δ</sup>		
	Floors for RCB and RFB structures on rock or a seal course - minimum before erecting forms and reinforcing steel							2 4		
	Floors for RCB and RFB structures on s - minimum before erecting forms and re	inforcing	steel		43 N			<sup>∆</sup> [2]*		
	Do not remove forms or falsework from post tensioned elements until all applied post tensioning forces are transferred.									




End.
Thanks !!!





### **Substructures**



# **Types of Substructures**

- Types of Substructures
  - Abutments
    - Used at the ends of the bridge to retain the embankment and carry the vertical and horizontal loads from the superstructure to the substructure.
  - Pier
    - Element supporting the superstructure located between the bridge abutments.
  - Walls
    - MSE Mechanically Stabilized Earth.



3


# **Types of Abutments 1**







# **Types of Abutments 2**





5


# **Abutment Wings**

- Straight Wings
  - Wings are aligned with abutment
  - Most used
  - Whenever possible, KDOT prefers the use of straight wings.
- U-Type
  - Wings are parallel to roadway
  - Used when grading around the bridge is restricted and/or there are other geometric restrictions.



#### **Abutment Foundations**

- Pile Bent Abutments
  - Most common
- Column Bent Abutments
  - Used only when required by geology or when other special conditions exist.
  - Pedestal Type Abutment






7

### **Abutment Berm Considerations**



Improper Berm Placement!





#### **Abutment MSE Wall Considerations**



- Flexible Element
  - MSE Wall
- Inflexible Element
  - Bridge Abutments
- Allow elements to move independently



a

### **Types of Piers**

- Pile Bent Piers (Wall Pier)
  - A row of multiple piles encased in a concrete webwall
  - Economical and normally used on low-level, short-span bridges.
  - Generally not used for grade separations
- Column Bent Piers
  - Typically 3 to 5 columns for standard roadway widths.
- Single Column Piers (Hammer Head Pier)
  - More economical when used in high level bridges or in large river crossings.



## **Column Bent Pier**







11

## **Pile Bent Pier (Wall Pier)**





## **Single Column Pier (Hammer head)**









13


## **Construction of Substructures 1**





#### **Construction of Substructures 2**







15

#### **Abutment Construction 1**


- Abutments
  - · Soil foundation cut to grade, level clear of debris
  - Contractor may use a commercial grade concrete leveling pad. This
    also assists in placement of form work. Must be to grade, can not be
    considered part of structure.
  - Verify re-steel, bar size length, bends and spacing. Tied adequately.
  - Bar chairs in good condition. (epoxy bars = epoxy chairs)



### **Abutment Construction 2**

- Abutments
  - Check form measurements
  - · Check Bar spacing
  - Verify beam seats and/or girder chairs.
  - Girder Supports placed in the substructure concrete







17

## **Abutment Construction 3**








## **Abutment Construction 4**





19

## **Pier Construction 1**





#### **Pier Construction 2**

- Piers
  - Column Forms
    - · Check diameter
    - · Free of rust
    - Form release
    - · Not out of round
  - Column Rebar
    - · Check diameter
    - · Bar size / spiral spacing
    - Not racked





21

#### **Pier Construction 3**

- Pier Column
  - Verify re-steel, bar size, length, bends and spacing.
  - Tied adequately.
  - Verify lap lengths and embed lengths of rebar.
  - Check that forms are clean, and plumb.
  - Check that elevation of top of can is determined and cut dimension to top of concrete is recorded.
  - Determine if through bolts are being used.





# 708.3 CONSTRUCTION REQUIREMENTS

#### · a. Falsework Design.

 Do not place cast-in-place shear bolts, coil inserts or other devices used as falsework support in pier columns without the approval of the Engineer. Through bolts are permitted. Do not drill and grout bolts or other devices into the pier columns unless shown in the Contract Documents.





23

#### **Pier Construction 4**

Bottom of Pier Cap Elevation / Top of Can Elevation





## 710.3 Construction Requirements 1

#### b. Handling and Placing Concrete

- Place concrete to avoid segregation of the materials and displacement of the reinforcement.
- Fill each part of the form by depositing the concrete as near to the final position as possible.
  - Do not drop concrete in the forms a distance of more than 5 feet, unless confined by clean, smooth, closed chutes or pipes.
- Obtain sample concrete for slump and air test requirements at the discharge end of the piping.
- Do not use chutes, troughs or pipes made of aluminum.



25

#### **Concrete Placement 1**







#### **Concrete Placement 2**







27

## 710.3 Construction Requirements 2

#### · g. Removal of Forms and Falsework

- Do not remove forms and falsework without the Engineer's approval.
- Do not remove forms and falsework until the minimum amount of time required for strength gain has elapsed regardless if the concrete is fully cured per Table 710-1
- Under normal conditions, the Engineer will allow removal of forms and falsework according to Table 710-3



## 710.3 Construction Requirements 3

- Table 710-1: Minimum Cure Times and Curing Mediums
- Table 710-2: Concrete Load Limitations on Bridge Decks
- Table 710-3: Minimum Strength Gain Time Before Removal of Forms & Falsework (Days)



TABLE 710-1; MIN	NIMUM CUR	E TIMES AND CURING MEDIUMS	
Type of Work	Minimum Cure Time (days)	Curing Medium and Use	
Bridge decks (full-depth decks with multi-layer polymer overlays)  Bridge subdecks (decks with overlays)	14 Wet	Saturated burlap covered with white polyethylene sheeting during the 14-day period. See <b>subsection 710.3e.(5)</b> .	
Bridge decks (full-depth decks with no overlay) Bridge Overlays (new and existing structures)	14 Wet Plus 7 Curing Membrane	Saturated burlap covered with white polyethylene sheeting during the 14-day period. See subsection 710.3e.(5).  After the wet cure period, apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat within 30 minutes of removing the sheeting and saturated burlap. Spray the second coat immediately after and at right angles to the first application.  Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.	Kansas  Department of Transportation
Other unformed or exposed surfaces	7 Curing Membrane	Apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat immediately after completion of the concrete finish just as the surface water disappears. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period. Should the compound be subjected to continuous damage, the Engineer will require saturated burlap, white polyethylene sheeting or other approved impermeable material to be applied at once for the remainder of the cure time.	Table 710-1
Formed sides and ends of bridge wearing surfaces and bridge curbs Other formed surfaces	4 Formed	Formed surfaces will be considered completely cured upon the Engineer's permission to remove the forms, providing the forms have been in place for a minimum of 4 days.  If forms are removed before the end of the 4-day cure period, cure the surface with an application of Type 1-D liquid membrane forming compound.	

er Greater					
20 than 30					
15 <sup>Δ</sup> [10] <sup>+</sup>					
Type of Work Time (Days)**					
4 <sup>Δ</sup> [3]*					
Footing Supported on Piles - minimum cure before erecting forms and reinforcing steel for columns $4^{\delta}[2]^*$					
2 △					
Columns for cantilevered piers -  1. minimum before supporting forms and reinforcing steel for the pier beam on the column. $4^{\Delta}[2]^{+}$					
4 ^ [2]+					



#### **Table 710-3**

Contractors may reduce the time required before form removal to the number of days shown in brackets, provided the oncrete is shown to have attained a minimum strength of 65% of the specified 1°. To accomplish this, prepare the necessary yillnders, obtain the services of an approved laboratory to break them at the appropriate time and provide a report to the ingineer. Field cure the cylinders alongside and under the same curing conditions, as the concrete they represent.

\*P Do not set girders or beams on the pier beams until the falsework under the pier beams is removed. \*\*Remove the formwork florm subdecks or one-course decks within in weeks after the deck has been placed. \*\*Contractors may reduce the time required before form removal to the number of days shown in brackets, provided the oncrete is shown to have attained a minimum strength of 75% of the specified 1°. To accomplish this, prepare the necessary yillnders, obtain the services of an approved alboratory to break them at the appropriate time and provide a report to the rigineer. Field cure the cylinders alongside and under the same curing conditions, as the concrete they represent.

\*Increase the time period 3 days when supplemental cementifious materials are used October 1 thru April 30.

\*\*See SECTION 2044.

31

tensioning forces are transferred.

Floors for RCB and RFB structures on rock or a seal course

Floors for RCB and RFB structures on rock or a seal course

- minimum before erecting forms and reinforcing steel

Floors for RCB and RFB structures on soil or foundation stabilization

- minimum before erecting forms and reinforcing steel

Do not remove forms or falsework from post tensioned elements until all applied post

## **Table 710-1 Example**

What is the minimum cure time required for a formed bridge abutment beam to be considered completely cured? What must be done if the forms are removed before the end of the specified cure period?

2 4

44[2]\*

Formed sides and ends of bridge wearing surfaces and bridge curbs  Other formed surfaces  Other formed surfaces  Upon the Engineer's permission to remove the for providing the forms have been in place for a minim of 4 days.  If forms are removed before the end of the 4-day of period, cure the surface with an application of Type liquid membrane forming compound.	wearing surfaces and bridge curbs
---	-----------------------------------



#### **Table 710-3 Examples 1 & 2**

- Q1: A drilled shaft was poured on April 15<sup>th</sup>. The drilled shaft concrete used supplemental cementitious materials. What is the minimum strength gain time required before erecting forms and reinforcing steel for the columns?
- Q2: The columns for a bent pier were poured on May 1<sup>st</sup>. What is the minimum number of days required before erecting formwork and reinforcing steel for the pier beam? What is the minimum number of days before placing concrete for the pier beam? Assume no concrete cylinders have been tested.



33

## **Table 710-3 Examples 3 & 4**

- Q3: A pier beam for a column bent pier with falsework supporting the pier beam was poured on May 15<sup>th</sup>. The spans between the columns are 15'-0". Concrete cylinders were tested and broke at 70% of the specified f'c. What is the minimum strength gain time before removing the forms for the pier beam?
- Q4: What is the minimum strength gain time for the removal of forms from an abutment? Assume no supplemental cementitious materials were used and no concrete cylinders have been tested.



### Table 710-3 Examples (Q1)

Drilled shafts - minimum before erecting forms and reinforcing steel for the columns

2 △

- <sup>∆</sup> Increase the time period 3 days when supplemental cementitious materials are used October 1 thru April 30.
- Since supplemental cementitious materials were used and the date was between October 1<sup>st</sup> and April 30<sup>th</sup>, the minimum strength gain time required before erecting forms and reinforcing steel for the columns is 5 days.



35

### Table 710-3 Examples (Q2)

Columns for bent piers -

1. minimum before erecting formwork and reinforcing steel for the pier beam

2 <sup>Δ</sup> 4 <sup>Δ</sup> [2]\*

- 2. minimum before placing concrete for the pier beam
  - <sup>∆</sup> Does not apply due to the date, even if supplemental cementitious materials were used.
  - \* Does not apply because the contractor did not break cylinders.
- The minimum number of days required before erecting formwork and reinforcing steel for the pier beam is **2 days**.
- The minimum number of days before placing concrete for the pier beam is **4 days**.



## Table 710-3 Examples (Q3)

TABLE 710-3: MINIMUM STRENGTH GAIN TIME BEFORE REMOVAL OF FORMS & FALSEWORK (DAYS)								
	Span Length (feet)							
Type of Work	Less than 10	10 or less	Greater than 10	10 to 20	20 + to 30	Greater than 20	Greater than 30	
Cantilevered Piers - Formwork (supporting the pier beam) supported on column		7 <sup>^</sup> [4]*	10 <sup>A</sup> [6]*					
Column Bent Piers - Falsework supporting pier beam**	4 ∆			7∆ [4]*		10∆ [6]*		
Forms and Falsework under slabs, beams, girders, arches and brackets***	4 <sup>A</sup>			7△ [4] <sup>+</sup>	10∆ [6]⁺		15 <sup>∆</sup> [10] <sup>+</sup>	
RCB and RFB top slabs not re-shored		7∆ [4]+		7∆ [4]⁺		10 <sup>∆</sup> [6] <sup>+</sup>		

- <sup>∆</sup> Does not apply due to the date, even if supplemental cementitious materials were used.
- \*Does apply because the concrete was shown to have attained at least 65% of f'c.
- The minimum strength gain time before the removal of forms and falsework for the pier beam is 4 days.



37

## Table 710-3 Examples (Q4)

Time (Days)++

4<sup>Δ</sup>[3]\*

Type of Work

Walls, Wing Walls and vertical sides of RCB and RFB structures

- Walls, Wing Walls and vertical side of RCB and RFB structures would apply to abutments.
  - <sup>Δ</sup> Does not apply because supplemental cementitious materials were not used.
  - \* Does not apply because the contractor did not break cylinders.
- The minimum strength gain time is **4 days**.



## **Measurement and Payment**


- Concrete Structure Construction 710.4
  - The Engineer will measure the various grades of concrete placed in the structure by the cubic yard. No deductions are made for reinforcing steel and pile heads extending into the concrete.
- Reinforcing Steel 711.4
  - The Engineer will measure the reinforcing steel by the pound, based on the theoretical number of pounds shown in the Contract Documents or placed as ordered in writing by the Engineer.









#### **Superstructures**







#### **Reinforced Concrete Haunched Slab**



- Maximum Span = 72'
- Falsework
  - A GREAT deal of Falsework Required
- Heavy Reinforcement
- Lengthy Curing Period
- Very Stout Bridge



5

### **RCSH Falsework**








### **Parabolic Haunch Formula**

- Theory
  - The vertical ordinate will vary with the square of the distance from the PC.
  - Any Ordinate =  $\frac{(\text{distance from PC})^2 * b}{a^2}$
  - Area = (a\*b)/3





7

## **RCSH Reinforcing Steel**





#### **Prestressed Concrete Beam/Girder**

- Spans from 60' to 110' are typical
- Component Construction
  - Rapid Assembly
- Special Deck Forming Considerations
  - Temporary Diaphragms
  - Camber Correction
  - Overhangs
  - Composite Designs





9

### **Fabrication**







#### Structural Steel Beam / Girder 1

- Generally Longer Spans > 110'
  - Lewis and Clark Viaduct Maximum Span = 375'
- · Bolting and Welding Required
  - Experienced Labor and Inspection
- Special Deck Forming
- Very Flexible
- May Require Painting



11


#### Structural Steel Beam / Girder 2





#### **Structural Steel Girder 3**

- Basic Parts
  - Flanges
  - Webs
  - Stiffener
    - Bearing
    - Intermediate
    - Connection
    - Longitudinal
    - Girder Ends
  - · Cross-Frames / Diaphragms
  - Bolts and Splices
  - Studs (field applied or shop applied)





13

### Structural Steel Beam / Girder 4







#### Structural Steel Beam / Girder 5





15

## **Steel Bridge Construction 1**

- Basic Beam/Girder Types
  - Rolled Beam
    - From the mill
    - I shaped
    - Mill camber only (no vertical curve or dead load camber)
    - · Usually not horizontally curved
  - Plate Girder
    - · Fabricated from plates in the shop
    - I shaped
    - · Cambered for vertical dead load
    - · Can be horizontally curved



#### **Steel Bridge Construction 2**

- Basic Materials
  - Weathering Steel (members, fasteners, washers, and DTI's)
    - · Top of top flange painted
    - 2D way from joint painted, Encased +2 inches
    - · Fascia and bottom on Plate girders with drainage over the side
  - Non-Weathering Steel (Painted)
  - Galvanized (Joints)



17

#### **Structural Steel - Erection**

- The contractor will provide:
  - Detailed plan for the erection of the structure (not for simple structures).
  - · Shop details.
  - Camber diagrams.
  - List of field bolts (lot numbers and certifications).
  - Copy of the shipping statement showing a list of parts and their mass.

- Three Steps to Structural Steel Erection
  - 1. Assembly
  - 2. Fit-Up
  - 3. Bolting
- These are three separate inspectable operation.
- Successful erection relies on proper substructure construction.



### **Steel Bridge Construction 3**

- Erection Bolt must be clearly identifiable as an erection bolt. They are the contractor's property and are only for contractor's ease of erection. They are not production bolts.
- Production bolts will arrive to the job in sealed kegs, tubs, or buckets. They will have their producer's mark and grade stamped on the head. Once a production bolt has been fully tightened it may not be retightened and used as a production bolt. It has become an erection bolt.



## Bridge Decks & Bridge Deck Overlays

Decks: 400 (Mud) & 700 (Structures)

Overlays: 731 (Area Prep. for Patching), 732 (Machine Prep.), 717 (Conc. OL), 729 (Poly OL)

BD-1

1

## 710.3 Construction Requirements

- · Get very familiar with this specification!!!!
- · Lots of information, won't be able to cover all of it
- Know <u>where</u> to look



## 710.3 - CONSTRUCTION REQUIREMENTS (b. Handling & Placing Conc.) p. 700-40

b. Handling and Placing Concrete. At a progress project meeting prior to placing concrete, discuss with the Engineer the method and equipment used for deck placement; include the equipment for controlling the evaporation rate, procedures used to minimize the evaporation rate, and method to place saturated burlap within the specified 15 minute limit.

Fogging using hand-held equipment may be required by the Engineer during unanticipated delays in the placing, finishing or curing operations. If fogging is required by the Engineer, do not allow water to drip, flow or puddle on the concrete surface during fogging, placement of absorptive material, or at any time before the concrete has achieved final set.

When needed, produce a fog spray from nozzles that atomize the droplets and a system capable of keeping a large surface area damp without depositing excess water. Use high pressure equipment that generates a minimum of 1200 psi at 2.2 gpm, or low pressure equipment having nozzles capable of supplying a maximum flow rate of 1.6 gpm.

Use a method and sequence of placing concrete approved by the Engineer. Do not place concrete until the forms and reinforcing steel have been checked and approved. Before placing concrete, clean all forms of debris. Drive all foundation piling in any one pier or abutment before concrete is poured in any footing or column of that pier or abutment.

On bridges skewed greater than 10°, place concrete on the deck forms across the deck on the same skew as the bridge, unless approved otherwise by State Bridge Office (SBO). Operate the bridge deck finishing machine on the same skew as the bridge, unless approved otherwise by the SBO.

Maintain environmental conditions on the entire bridge deck such that the evaporation rate is less than 0.2 lb/sq ft/hr. This may require placing the deck at night, in the early morning or on another day. The evaporation rate (as determined in the American Concrete Institute Manual of Concrete Practice 305R, Chapter 2) is a function of air temperature, concrete temperature, wind speed and humidity.


Kansas

3

# 710.3 Construction Requirements b. Handling & Placing Concrete

- Project Progress Meeting
  - Method and Equipment for deck placing
  - Evaporation rate control equipment
  - Method to place burlap in 15-minute limit
- Skewed bridges greater than 10° will place concrete on the skew unless stated otherwise by the State Bridge Office
  - Same goes with Finishing
- · Maintain an evaporation rate of less than 0.2 lb/sqft/hr
  - Figure 710-1





## Evaporation Rate Chart, Fig. 710-1, p. 700-42

- 62° ambient temperature
- 52% relative humidity
- 60 concrete temperature
- 20 mph wind velocity


Effect of concrete and air temperatures, relative humidity, and wind velocity on the rate of evaporation of surface moisture from concrete. This chart provides a graphic method of estimating the loss of surface moisture for various weather conditions. To use the chart, follow the four steps outlined above. When the levaporation rate exceeds  $0.2 \ln^{17} \ln^4 (1.0 \log^4 m^2/\ln^2)$ , measures shall be taken to prevent excessive moisture loss from the surface of unhardened concrete, when the rate is less than  $0.2 \ln^{17} \ln^4 (1.0 \log^2 m^2/\ln^2)$  such measures may be needed. When excessive moisture loss is not prevented, plastic cracking is likely to occur.

(Fog/ with Wind Breaks)

. \_ \_ \_

(No Fog)





## 710.3 - CONSTRUCTION REQUIREMENTS (b. Handling & Placing Conc.) p. 700-40

Just prior to and at least once per hour during placement of the concrete, the Engineer will measure and record the air temperature, concrete temperature, wind speed and humidity on the bridge deck. The Engineer will take the air temperature, wind and humidity measurements approximately 12 inches above the surface of the deck. With this information, the Engineer will determine the evaporation rate by using KDOT software or by using FIGURE 710-1 (Figure 2.1.5 from the American Concrete Institute Manual of Concrete Practice 305R, Chapter 2).

When the evaporation rate is equal to or above 0.2 lb/ft²/hr, take actions (such as cooling the concrete, installing wind breaks, sun screens etc.) to create and maintain an evaporation rate less than 0.2 lb/ft²/hr on the entire bridge deck

Place concrete to avoid segregation of the materials and displacement of the reinforcement. Do not deposit concrete in large quantities at any point in the forms, and then run or work the concrete along the forms.

Deposit the concrete in the forms in horizontal layers. Perform the work rapidly and continuously between predetermined planes. Vibrate through each plane.

Fill each part of the form by depositing the concrete as near to the final position as possible. If the chutes for placement of concrete are on steep slopes, equip them with baffle boards or assemble in short lengths that reverse the direction of movement. Do not drop concrete in the forms a distance of more than 5 feet, unless confined by clean, smooth, closed chutes or pipes.

Work the coarse aggregate back from the forms and around the reinforcement without displacing the bars. After initial set of the concrete, do not disturb the forms, or place any strain on the ends of projecting reinforcement.

If placing concrete by pumping, place the concrete in the pipeline to avoid contamination or separation of the concrete, or loss of air by fitting the pump with a concrete brake (e.g. french horn or bladder valve) at the end of the pump boom. Obtain sample concrete for slump and air test requirements at the discharge end of the piping.

Do not use chutes, troughs or pipes made of aluminum.

Uniformly consolidate the concrete without voids.





Pump Truck circa 1990





(Take mud samples from wherever the boom is during deck placement to get representative sample.)



9

#### (b. Handling & Placing Conc.) p. 700-40

Accomplish consolidation of the concrete on all span bridges that require finishing machines by means of a mechanical device on which internal (spud or tube type) concrete vibrators of the same type and size are mounted (subsection 154.2). Observe special requirements for vibrators in contact with epoxy coated reinforcing steel as specified in subsection 154.2. Provide stand-by vibrators for emergency use to avoid delays in case of failure.

Operate the mechanical device so vibrator insertions are made on a maximum spacing of 12-inch centers over the entire deck surface. Provide a uniform time per insertion of all vibrators of 3 to 15 seconds, or until the course aggregate settles below the surface of the concrete, unless otherwise designated by the Engineer. Provide positive control of vibrators using a timed light, buzzer, automatic control. Smoothly extract the vibrators from the concrete at a rate to avoid leaving any large voids or holes in the consolidated concrete. Do not drag the vibrators horizontally through the concrete.

Use hand held vibrators (subsection 154.2) in inaccessible and confined areas such as along hubguards. When required, supplement vibrating by hand spading with suitable tools to provide required consolidation. Reconsolidate any voids left by workers.

The method used for transporting concrete batches, materials or equipment over previously placed single pour (non-overlaid) floor slabs or floor units, or over units of structures of continuous design types is subject to approval by the Engineer.


Do not operate bridge deck finishing equipment on previously placed concrete spans until:

- A minimum of 72 hours on structures that are fully supported with falsework; (Haunched Slabs)
- A minimum of 72 hours on structures with concrete girder spans with concrete decks; and (Prestressed)
- A minimum of 96 hours on structures with steel girder spans with concrete decks.

(Plate Girders or Rolled Beams)


The time delays begin after the day's pour has been completed. Follow TABLE 710-2 for load limitations after concrete placement. Prior to permitting approved traffic on the bridge deck, construct temporary bridge approaches and maintain them in a condition to prevent damage to the ansacs bridge ends







(Mud placement, Single Drum Screed, Gang Vibrators) (CHECK/RECORD Cover & Fillet Depths at 10<sup>th</sup> Points)









## 710.3 - CONSTRUCTION REQUIREMENTS

**d. Finishing.** Finish all top surfaces, such as the top of retaining walls, curbs, abutments and rails, with a wooden float by tamping and floating, flushing the mortar to the surface and provide a uniform surface, free from pits or porous places. Trowel the surface producing a smooth surface, and brush lightly with a damp brush to remove the glazed surface.

Strike off bridge decks with a self-propelled finishing machine, which may be manually operated by winches to reach a temporary bulkhead when approved by the Engineer. The screed on the finish machine must be self-oscillating, and operate or finish from a position either on the skew or transverse to the bridge roadway centerline.

On decks skewed greater than 10°, operate the finishing machine on the same skew as the bridge, unless approved otherwise by the SBO. Before placing concrete, position the finisher throughout the proposed placement area allowing the Engineer to verify the reinforcing steel positioning.

Irregular sections may be finished by other methods approved by the Engineer. Reinforced concrete box bridges that will be under fill may be struck off by other approved methods.

Float and straightedge the wearing surface so the finished surface is at the cross-section shown in the Contract Documents. Do not add water to the surface of concrete, unless approved by the Engineer, and when approved apply as a fog spray.

Secure a smooth riding bridge deck, correcting surface variations exceeding 1/8 inch in 10 feet by use of an approved profiling device, or other method approved by the Engineer.

Straightedge decks that are to receive an overlay, leaving them with an acceptable float or machine pan finish

For decks not receiving an overlay, and without the bid item Bridge Deck Grooving, finish the deck with the rough burlap drag.

For decks not receiving an overlay, and with the bid item Bridge Deck Grooving, see subsection 710.3f. for grooving requirements.





Float Train c. '90 (Transverse Grooving now done by multi-blade diamond arbor, see Sub-Sec. f., p. 700-46)



## 710.3 - CONSTRUCTION REQUIREMENTS (e. Curing & Protection) p. 700-44

e. Curing and Protection.

(1) General. Cover concrete surfaces according to **TABLE 710-1**. Cure all pedestrian walkway surfaces in the same manner as the bridge deck. The determination of the time requirement for curing commences after all the concrete for the placement is in place and finished. During cold weather, the specified time limits may be increased at the discretion of the Engineer, based upon the amount of protection and curing afforded the concrete.

Maintain a damp surface until the wet burlap is placed. Fully saturate burlap before placing on concrete surface. Cover all concrete surfaces with saturated burlap within 15 minutes after finishing the concrete, do not mar concrete during placement of the wet burlap. Maintain the curing so that moisture is always present at the concrete surface.

Place and weight down the burlap so it will remain in intimate contact with the surface covered

When an impermeable sheeting material is used, lap each unit 18 inches with the adjacent unit. Place and weight down the impermeable sheeting material so it will remain in intimate contact with the surface covered. When any burlap or impermeable sheeting material becomes perforated or torn, immediately repair it, or discard and replace it with acceptable material.

TABLE 710-1: MINIMUM CURE TIMES AND CURING MEDIUMS					
Bridge decks (full-depth decks with no overlay) Bridge Overlays	14 Wet Plus 7 Curing Membrane	Wet burlap covered with white polyethylene sheeting during the 14-day period.  After the wet cure period, apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat within 30 minutes of removing the sheeting and burlap. Spray the second coat immediately after and at right angles to the first application.  Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.			





17

## 710.3 - CONSTRUCTION REQUIREMENTS (e. Curing & Protection) p. 700-44









## 731 – AREA PREP. FOR PATCHING (a. General p. 700-116)

#### 731.3 CONSTRUCTION REQUIREMENTS

**a. General (All Decks).** Remove asphalt material and unsound concrete as shown in the Contract Documents and as designated by the Engineer, to the depth required to reach sound concrete and rust free reinforcing steel. Dispose of removed material on sites approved by the Engineer.

Unless specifically noted in the Contract Documents, the Contractor may choose to remove unsound concrete by other means capable of removing the required concrete, without injury to the sound concrete and reinforcing steel.

Unless specifically noted in the Contract Documents, the Contractor may **not** choose to remove unsound concrete by hydrodemolition. When hydrodemolition is allowed, remove the required concrete, without injury to the sound concrete and reinforcing steel. When hydrodemolition is allowed and used as the method of removal, the Engineer will determine the areas of unsound concrete after hydrodemolition.

Do not use jack hammers or chipping hammers heavier than the nominal 15-pound class on any partial depth concrete removal. Jack hammers up to the nominal 30-pound class may be used in areas of full depth patching to within 6 inches of the edges of the designated areas. Do not use chipping hammers heavier than a nominal 15-pound class to remove the 6-inch edge. Operate jack hammers and chipping hammers at an angle to prevent damage to the sound concrete.



21




- 1. Locate and mark beams if working on a steel structure.
- Work carefully to <u>NOT</u> gouge or damage Top Flange during removal.
- 3. If damaged, beams will be repaired at No Cost to the State.





### Fig. 731-1 is CONFUSING!!

(1) Reinforcing. Remove all scale and heavy rust from steel bars. When concrete is removed by jack hammers, wet sandblasting is prohibited. If reinforcing is left exposed, and signs of rust appear, the Engineer may require that the cleaning be repeated. Do not cut, stretch or damage any exposed reinforcing steel. Do not break the bond between the reinforcing steel and concrete where bars are partially exposed yet remain anchored in sound concrete, near the ends or where more than half the bar is beneath the concrete removal line. See FIGURE 731-1.




23

#### 731 - AREA PREP. FOR PATCHING (a. General p. 700-116)

(2) Bonding of Reinforcing Steel.


(a) Top Layer of Transverse Reinforcing Bars. Where the bond between existing concrete and the top layer of transverse reinforcing steel has been destroyed (FIGURE 731-2), remove the concrete adjacent to the bar to a depth that shall permit concrete to bond to the entire periphery of the bar with a minimum clearance of ¾ inch. A bar may be considered bonded by the Engineer even if less than ½ the bar depth is embedded in concrete.

#### FIGURE 731-2



(b) All Reinforcing Bars Other Than the Top Layer of Transverse Bars. Where more than  $\frac{1}{2}$  the diameter of the steel is exposed (FIGURE 731-3), or where the bond between existing concrete and reinforcing steel has been destroyed (FIGURE 731-2), remove the concrete adjacent to the bars to a depth that shall permit concrete to bond to the entire periphery of the bar with a minimum clearance of  $\frac{3}{4}$  inch.





CHINE PREPARATION ( ): This item shall consist of preparing the deck for a SFO by removing concrete from the roadway surface of the bridge deck to a depth of inches. See KDOT Specifications.

of inches, See KUUT Specifications.

APEA PREPARED FOR PATCHING The time shall consist of removing unsound concrete and bituminaus patches from the bridge deek, cleaning reinforcing box filling the removed patched areas with concrete and preparing the entire area of the deck for \$50. Quantity shown is an estimate of the areas involved. The exact areas shall be elemented by trappic, before, during and direct chipsing or exactly approached, auting and after chipsing creamed. See KOOT Specifications.

FEMILE DEFTH ATCHING. Forms shall be provided to enable placement of concrete in areas of full depth removal of bridge stab. The forms may be asspended from existing reinforcing bars by wire ties or a method approved by the Engineer may be used. See KDOT Specifications for method of measurement and basis of payment.


method or meosurement was a source of the REINFORCING IN BRIDGE DECK: Core should be exercised it prevent cutting, stretching or dramaging exposed reinforcing steel. Extreme core should be exercised to avoid brooking the bond between the reinforcing steel and concrete where bors are portfully exposed yet remain anchored in sound concrete. Briefracting steel dramagod, cut or deterior drea shell be replaced as directed by the Engineer. See table


SILICA FUME OVERLAY CONSTRUCTION JOINTS: All vertical construction joints in the overlay and the vertical joint between the overlay and the curbs shall be cleaned by sandblasting, and then pointing the joints with an approved Concrete Mesony Costing 72 hours after placement of the Silica Fume Overlay.

REPAIR OF EPOXY COATED REINFORCING STEELs Replace any epoxy coefing that is removed from the reinforcing steel during the concrete removal prosess. Thoroughy clean damaged cross with a stiff wire brush to remove dirt and damaged coding. Apply on approved patching material in accordance with manufacturer's recommendations. Avaid dripping any patching indirect and our auditing concrete that will have new concrete placed against 11. See KDCT Specifications.



25





#### 732 – MACHINE PREP. (p. 700-121)

#### 732.1 DESCRIPTION

Prepare the bridge deck surface for a concrete bridge deck overlay by removing the existing concrete and asphaltic material from bridge deck and approaches as shown in the Contract Documents.

BID ITEM
Machine Preparation (\*)
\*Thickness

UNITS Square Yard

732.2 MATERIALS - None specified.

#### 732.3 CONSTRUCTION REQUIREMENTS

Remove concrete and asphaltic materials from the existing surface to the specified depth over the area of the deck by means of milling or cutting procedure capable of removing the specified material without injury to the sound concrete.

When specified, mill the approaches according to the Contract Documents.

#### 732.4 MEASUREMENT AND PAYMENT

The Engineer will measure machine preparation by the square yard. Milling of approaches is subsidiary to the machine preparation bid item.

Payment for "Machine Preparation" at the contract unit price is full compensation for the specified work.



## 717 – BRIDGE OVERLAYS p. 700-91

#### 717.1 DESCRIPTION

Construct the portland cement concrete overlay as shown on the Contract Documents.

When Bridge Deck Grooving is a bid item in the contract, perform the grooving as shown in the Contract Documents.

BID ITEMS
Portland Cement Concrete Overlay (\*)
Material for Portland Cement Concrete Overlay (Set Price)
Bridge Deck Grooving
Thickness
Square Yard

#### 717.2 MATERIALS

Provide materials that comply with the applicable requirements.

Grade 4.0 (AE) Concrete \* SECTIONS 401 & 402
Aggregate for Concrete Not On Grade DIVISION 1102
Precure/Finishing Aid Material \* DIVISION 1400
Concrete Curing Materials DIVISION 1400
Concrete Masonry Coating DIVISION 1700
\*Use concrete that meets requirements for low permeability concrete (LPC) as specified in DIVISION 400.

\*\*When silica fume is used as an SCM, the use of Precure/Finish Aid may be used according to the manufacturer's instructions.

For overlays use Supplemental Cementitious Materials at allowable substitution rates as listed in TABLE 401-2.



Kansas

29

## 717.3 – BRIDGE OVERLAYS – Const. Req. (b. Surface Prep.) p. 700-92

TABLE 717-1: PORTLAND CEMENT CONCRETE OVERLAY PRODUCTION REQUIREMENTS			
Total Placed Surface Area per Bridge (Square Yards)	Minimum Cubic Yards per Hour		
0-328	1.0		
329-492	1.5		
493-656	2.0		
Over 656	2.5		

b. Preparation of Surface. Prior to placement of concrete, sand or shot blast the surface followed by an air blast to the bottom 3 inches of hubguard, and edges against which concrete is to be placed to remove all dirt, oil, pavement marking and other foreign material, as well as any unsound concrete, laitance and curing material from the surface. Wet sand blasting may be used only with approval of the Engineer. It is desired that the surface be roughened by the sand or shot blast to provide satisfactory bond with the surfacing concrete. Protect metal deck drains and areas of the curb or railing above the proposed surface from the sand or shot blast.

Check the finish machine clearance above the prepared surface before concrete is placed to obtain the thickness specified in the Contract Documents.

A minimum of 2 hours before the placing of the concrete overlay, use clean water to thoroughly wet any concrete surfaces to which the concrete is to bond against. Blow or broom away all free water immediately ahead of the placing operation. Bonding surfaces should be maintained in a damp condition with no free water.

## 717.3 – BRIDGE OVERLAYS (c. Placing Concrete) p. 700-92

c. Placing Concrete. Place and fasten the screed rails in position to obtain finished concrete at the required profile. Place the supporting rails upon which the finishing machine travels outside the area to be concreted. A hold-down device shot into concrete is prohibited, unless the concrete is to be subsequently overlaid. Hold-down devices of other types leaving holes in exposed areas will be approved provided the holes remaining are grouted full. Methods for anchoring and supporting the rails and the concrete placing procedure require approval by the Engineer.

Locate longitudinal joints along lane lines, or as approved by the Engineer. Keep the joints clear of wheel paths as much as practical.

Placing of the overlay is prohibited when conditions on the bridge deck are such that the evaporation rate is estimated to equal or exceed 0.2 pounds per square foot per hour, or is predicted to exceed that rate during the course of the placement, unless corrective measures listed in **subsection 710.3b.** are taken to reduce the evaporation rate to below 0.2 pounds per square foot per hour.

Fogging may be necessary during placement of the overlay. Accomplish fogging according to subsection 710.3b.

The evaporation rate will be rechecked with the measures in place, using the procedures outlined above.

The elapsed time between depositing the concrete on the deck and final screeding may not exceed 15 minutes, unless otherwise authorized by the Engineer.

Manipulate and mechanically consolidate new concrete to a minimum of 98% of the consolidated unit weight and screed to final grade. In irregular areas or along the curb where the finishing screed does not reach, hand tamp with a 6-inch by 6-inch metal plate device to assist in consolidation and bonding of the concrete. When concrete for partial depth patches is placed with the overlay, apply additional vibration or hand tamping in the patch areas to assist in consolidation and bonding of the concrete.

31

## 717.3 – BRIDGE OVERLAYS (f. Weather Limitations) p. 700-93

**f. Weather Limitations.** See **SECTION 401**. Also, discontinue concreting operations when a descending air temperature in the shade and away from artificial heat falls below 45°F except with written approval from the Engineer. Do not start or resume operations until an ascending air temperature reaches 40°F, or if night time temperatures are expected to fall below 35°F.





Kansas

## 729 – MULTI-LAYER POLY OVERLAYS p. 700-109

#### 729.1 DESCRIPTION

Prepare the surface of the reinforced concrete bridge deck and construct a multi-layer polymer concrete overlay (overlay) as shown on the Contract Documents.

Provide an overall combination of labor and equipment with the capability of proportioning and mixing the polymer resin components and placing the primer and aggregate, in accordance with this specification and the manufacturer/supplier's recommendations.

#### **BID ITEM**

Multi-Layer Polymer Concrete Overlay

#### UNITS

Square Yard

#### 729.2 MATERIALS

#### a. General.

- (1) Proportion all polymer materials according to the manufacturer/supplier's recommendations.
- (2) Provide the Engineer with a copy of the polymer materials manufacturer/supplier's mixing and application recommendations.
- (3) If concrete bridge deck patching is specified, polymer concrete materials may be used for patching of the concrete bridge deck. See **SECTION 731**.
  - b. Epoxy. Provide a Type III epoxy resin as defined in DIVISION 1700
  - c. Polyester. Provide a polyester resin as defined in DIVISION 1700.

#### d. Aggregate.

- (1) Provide FA-C aggregate meeting TABLE 1102-5 and TABLE 1102-6, or
- (2) As provided by the polymer concrete overlay supplier in a prequalified system, DIVISION 1700.



33

## 729 – MULTI-LAYER POLY OVERLAYS p. 700-109

#### 729.3 CONSTRUCTION REQUIREMENTS

a. General. Wet cure concrete on new bridge decks for 14 days and allow the deck to dry for 21 days before applying the overlay.

Portland cement concrete patches require a minimum cure period of 28 days before application of the overlay

At the preconstruction conference, discuss the patching material and the corresponding curing period. Submit changes, including a written statement from the polymer manufacturer/supplier recommending changes, to the Engineer for approval.

**b. Equipment.** Equipment is subject to approval of the Engineer and must comply with these requirements:

(1) Surface Preparation Equipment

- (a) Shot blasting equipment capable of producing a surface relief equal to the International Concrete Repair Institute (ICRI) Surface Preparation Level 6 to 7 or ASTM E 965 Pavement Macrotexture Depth of 0.04 to 0.08 inch. Final acceptance is based on testing procedures as outlined in KT-70, Part V.
- (b) Shot/Sand blast equipment capable of producing the required surface relief on the deck adjacent to bridge rails and barriers and areas not accessible with shot blast equipment.
- (c) Empty shot blasters and dispose of waste material a minimum of 50 feet from the prepared bridge deck. On long structures empty shot blasters on the unprepared surface a minimum of 50 feet from prepared surface to prevent contamination of the deck by return of dust to the prepared surface.
- (d) The Engineer must approve the use of scarifiers, scrablers or milling machines.



#### 729 – MULTI-LAYER POLY OVERLAYS p. 700-110

(e) Wet sand blasting is prohibited.

(2) Mechanical Application Equipment.

- (a) Polymer mixing and distribution system capable of accurate and complete mixing of the polymer resin and hardening agent, verification of the mix ratio and uniform and accurate distribution of the polymer materials at the specified rate on 100% of the work area.
- (b) A self-propelled aggregate spreader (if required) capable of uniform and accurate application of the dry aggregate over 100 % of the work area.
- (c) An air compressor capable of producing a sufficient amount of oil free and moisture free compressed air to remove all dust and loose material.
- (d) Adequate additional hand tools to facilitate the placement of the polymer concrete overlay in accordance with this specification and the manufacturer/supplier's recommendations.

(3) Hand Application Equipment.

- (a) Calibrated containers for accurate measurement of the polymer components.
- (b) Paddle type mixer or other mixing device capable of accurate and complete mixing of the polymer resin and hardening agent.
- (c) Notched squeegees and brooms capable of spreading the polymer material in accordance with this specification and the manufacturer/supplier's recommendations.
- (d) Aggregate spreader capable of uniform and accurate application of the dry aggregate.
- (e) Adequate additional hand tools to facilitate the placement of the polymer concrete overlay in accordance with this specification and the manufacturer/supplier's recommendations.



35

## 729 – MULTI-LAYER POLY OVERLAYS p. 700-110

#### c. Preparation of Surface.

- (1) When specified, perform any required repairs under SECTION 731 and cure repairs, before preparation of the surface, unless placed with the overlay.
- (2) Protect metal deck drains and areas of the curb or railing above the proposed surface from the shot blast.
  - (3) Close deck drains so the overlay materials will not pass through the drains.
- (4) Remove any remaining contamination of the prepared deck surface or surface of subsequent courses. Sand blast or bush hammer contaminated areas to produce an acceptable surface for placement of the overlay.
- (5) As the final preparation for the placement of the overlay, make a complete cleanup by shot blasting and/or other approved means, followed by an air blast with dry, oil free air or vacuum. Brooming is not acceptable. Remove all pavement marking, loose disintegrated concrete, dirt, paint, oil, asphalt, laitance carbonation and curing materials from patches and other foreign material from the surface of the deck.
- (6) Produce a surface relief equal to the International Concrete Repair Institute (ICRI) Surface Preparation Level 6 to 7 or ASTM E 965 Pavement Macrotexture Depth of 0.04 to 0.08 inch.
- (7) Place the first coat of the overlay within 24 hours of preparing the deck surface. Prepared surfaces exposed for more than 24 hours must be lightly sand blasted prior to application of the overlay.



## 729 – MULTI-LAYER POLY OVERLAYS, Continued...

- d. Placing the Multi-Coat Poly
- e. Face of Curbs, Barriers and Rail
- f. Application Rates
- g. Curing
- h. Testing
- i. Correction of Unbonded Areas
- j. Weather Limitations

... Basically, if you get one of these Projects, read through it as best you can, then call Dan Wadley at Materials and he'll come out and help you.




37



Thanks!!!









1

- Curing mediums
  - Wet Burlap
  - Liquid membrane-forming compounds
  - White polyethylene sheeting
  - Formwork



#### 2.Curing - 15-07011-R01 - 710.3 e. Curing and Protection

(1) General. Cover concrete surfaces according to TABLE 710-1. Cure all pedestrian walkway surfaces in the same manner as the bridge deck. The determination of the time requirement for curing commences after all the concrete for the placement is in place and finished. During cold weather, the specified time limits may be increased at the discretion of the Engineer, based upon the amount of protection and curing afforded the concrete.

Maintain a damp surface until the saturated burlap is placed. Fully saturate burlap before placing on concrete surface. Cover all concrete surfaces with saturated burlap within 15 minutes after finishing the concrete, do not mar concrete during placement of the saturated burlap. When times of delay are expected to exceed 15 minutes, cover all concrete that has been placed, but not finished, with saturated burlap. Maintain the curing so that moisture is always present at the concrete surface.

Place and weight down the saturated burlap so it will remain in intimate contact with the surface covered.

When an impermeable sheeting material is used, lap each unit 18 inches with the adjacent unit. Place and weight down the impermeable sheeting material so it will remain in intimate contact with the surface covered. When any burlap or impermeable sheeting material becomes perforated or torn, immediately repair it, or discard and replace it with acceptable material.



3

TABLE 710-1: MINIMUM CURE TIMES AND CURING MEDIUMS				
Type of Work	Minimum Cure Time (days)	Curing Medium and Use		
Bridge decks (full-depth decks with multi-layer polymer overlays)  Bridge subdecks (decks with overlays)	14 Wet	Saturated burlap covered with white polyethylene sheeting during the 14-day period. See subsection 710.3e.(5).		
Bridge decks (full-depth decks with no overlay)  Bridge Overlays (new and existing structures)	14 Wet Plus 7 Curing Membrane	Saturated burlap covered with white polyethylene sheeting during the 14-day period. See subsection 710.3c.(5).  After the wet cure period, apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat within 30 minutes of removing the sheeting and saturated burlap. Spray the second coat immediately after and at right angles to the first application.  Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.		
Other unformed or exposed surfaces	7 Curing Membrane	Apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat immediately after completion of the concrete finish just as the surface water disappears. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period. Should the compound be subjected to continuous damage, the Engineer will require saturated burlap, white polyethylene sheeting or other approved impermeable material to be applied at once for the remainder of the cure time.		
Formed sides and ends of bridge wearing surfaces and bridge curbs Other formed surfaces	4 Formed	Formed surfaces will be considered completely cured upon the Engineer's permission to remove the forms, providing the forms have been in place for a minimum of 4 days.  If forms are removed before the end of the 4-day cure period, cure the surface with an application of Type 1-D		



### 4. Curing - 710.3 e. Curing and Protection

(2) Liquid Membrane Forming Compounds. Use spraying equipment capable of supplying a constant and uniform pressure to provide uniform distribution at the rates required. Agitate the liquid membrane forming compound continuously during application. The surface must be kept wet from the time it is finished until the liquid membrane forming compound is applied. Apply liquid membrane forming compound at a minimum rate per coat of 1 gallon per 200 square feet of concrete surface. Give marred or otherwise damaged applications an additional coating. If rain falls on the newly coated concrete before the film has dried sufficiently to resist damage from the rain, or if the film is damaged by any other means, apply a new coat of the membrane to the affected portion equal in curing value to the original application.



5

### 5. Curing - 710.3 e. Curing and Protection

(3) Bridge Subdecks and Decks. Provide a work bridge to facilitate application of all curing materials. Maintain the curing so that moisture is always present at the concrete surface.

Maintain the saturated burlap in a fully wet condition using misting hoses, self-propelled, machine-mounted fogging equipment with effective fogging area spanning the deck width, moving continuously across the entire burlapcovered surface, or other approved devices until the concrete has set sufficiently to allow foot traffic. At that time, place soaker hoses on the saturated burlap, and supply running water continuously to maintain continuous saturation of all burlap material to the entire concrete surface. For bridge decks with superelevation, place a minimum of 1 soaker hose along the high edge of the deck to keep the entire deck wet during the curing period.

If the concrete surface temperature is above 90°F, do not use polyethylene sheeting in direct sunshine during the day for the first 24 hours of the specified curing period (TABLE 710-1).



#### 6.Curing – 710.3 e. Curing and Protection

(5) Cold Weather Curing. If concrete is placed in cold weather, comply with SECTION 401. If concrete is placed and the ambient air temperature is expected to drop below 40°F during the entire specified curing period, prior to beginning concrete placement, provide materials on site to maintain the concrete temperature between 40 and 90°F as measured on the surface of the concrete. Suitable materials consist of straw, additional burlap or other blanketing materials or housing and artificial heat.

Keep the surface of the concrete moist by the use of an approved moisture barrier such as saturated burlap or polyethylene sheeting or both as defined in TABLE 710-1. Maintain the moisture barrier in intimate contact with the concrete during the entire specified curing period.

(6) Thermal Shock. After the completion of the required curing period, remove the curing and protection to prevent rapid cooling of the concrete so that the concrete temperature does not fall more than 25°F during the first 24 hours.



7

- Foundations and Substructures
  - In the Forms with Burlap and Poly
  - Footings
  - Abutments
  - Pier Columns and Caps






- Superstructure
  - Bridge Decks
  - Starts with Environmental Conditions
  - Evaporation Rate
  - < 0.2 lb/sq ft/hr
  - Fogging 1200
     psi / 2.2 gpm or
     low rate 1.6gpm





9

- Superstructure
  - Bridge Decks
  - Figure 710-1
  - Equal to or above 0.2 lb/ft2/hr, take actions to create and maintain an evaporation rate less than 0.2 lb/ft2/hr





- Superstructure
- Figure 710-1

Effect of concrete and air temperatures, relative humidity, and wind velocity on the rate of evaporation of surface moisture from concrete. This chart provides a graphic method of estimating the loss of surface moisture for various weather conditions. To use the chart, follow the four steps outlined above. When the evaporation rate exceeds 0.2 lb/ft2 /hr (1.0 kg/ m2 /hr), measures shall be taken to prevent excessive moisture loss from the surface of unhardened concrete; when the rate is less than 0.2 lb/ft2 /hr (1.0 kg/m2 /hr) such measures may be needed. When excessive moisture loss is not prevented, plastic cracking is likely to occur.



11

- Superstructure
- Cover within 15 minutes
- Fully Saturate burlap before placing on concrete surface





- Superstructure
- Place and weight down burlap so it will remain in intimate contact with the surface covered





13

- Superstructure
- Do not mar concrete during placement
- Maintain damp surface





- Superstructure
- Maintain the wet burlap in a fully wet condition
- Place Soaker Hoses, supply running water continuously





15

- Superstructure
- When impermeable sheeting is used, lap each unit 18"





- Superstructure
- If the concrete temperature is above 90 degrees, do not use polyethylene sheeting in direct sunlight for the first 24 hours





17

- 710.3 e. Curing
- Table 710-1
- Minimum Cure Times and Curing Mediums
- Note the specified type of liquid membrane

TABLE 710-1: MINIMUM CURE TIMES AND CURING MEDIUMS					
Type of Work	Minimum Cure Time (days)	Curing Medium and Use			
Bridge decks (full-depth decks with multi-layer polymer overlays)  Bridge subdecks (decks with overlays)	14 Wet	Wet burlap covered with white polyethylene sheeting during the 14-day period.			
Bridge decks (full-depth decks with no overlay) Bridge Overlays	14 Wet Plus 7 Curing Membrane	Wet burlap covered with white polyethylene sheeting during the 14-day period. After the wet cure period, apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat within 30 minutes of removing the sheeting and burlap. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.			
Other unformed or exposed surfaces	7 Curing Membrane	Apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat immediately after completion of the concrete finish just as the surface water disappears. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period. Should the compound be subjected to continuous damage, the Engineer will require wet burlap, white polyethylene sheeting or other approved impermeable material to be applied at once for the remainder of the curve time.			
Formed sides and ends of bridge wearing surfaces and bridge curbs Other formed surfaces	4 Formed	Formed surfaces will be considered completely cured upon the Engineer's permission to remove the forms, providing the forms have been in place for a minimum of 4 days.  If forms are removed before the end of the 4-day cure period, cure the surface with an application of Type 1-D liquid membrane forming compound.			



### Superstructures

TABLE 710-1: MINIMUM CURE TIMES AND CURING MEDIUMS				
Type of Work	Minimum Cure Time (days)	Curing Medium and Use		
Bridge decks (full-depth decks with multi-layer polymer overlays)  Bridge subdecks (decks with overlays)	14 Wet	Wet burlap covered with white polyethylene sheeting during the 14-day period.		
Bridge decks (full-depth decks with ho overlay) Bridge Overlays	14 Wet Plus 7 Curing Membrane	Wet burlap covered with white polyethylene sheeting during the 14-day period.  After the wet cure period, apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat within 30 minutes of removing the sheeting and burlap. Spray the second coat immediately after and at right angles to the first application.  Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.		



19

### 19.Curing

### • Superstructures

// / / / / / / / / / / / / / / / / / /	Other unformed or exposed surfaces	7 Curing Membrane	Apply 2 coats of Type 2 white liquid membrane forming compound. Place the first coat immediately after completion of the concrete finish just as the surface water disappears. Spray the second coat immediately after and at right angles to the first application. Protect the curing membrane against marring for a minimum of 7 days. The Engineer may limit work during this 7-day period.  Should the compound be subjected to continuous damage, the Engineer will require wet burlap, white
			polyethylene sheeting or other approved impermeable material to be applied at once for the remainder of the cure time.
2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Formed sides and ends of bridge wearing surfaces and bridge curbs Other formed surfaces	4 Formed	Formed surfaces will be considered completely cured upon the Engineer's permission to remove the forms, providing the forms have been in place for a minimum of 4 days.  If forms are removed before the end of the 4-day cure period, cure the surface with an application of Type 1-D liquid membrane forming compound.



- Superstructures
- Load Limits during cure period Table 710-2

TABLE 710-2: CONCRETE LOAD LIMITATIONS ON BRIDGE DECKS						
Days after concrete is placed	Element	Allowable Loads				
1*	Subdeck, one-course deck or concrete overlay	Foot traffic only				
3*	One-course deck or concrete overlay	Work to place reinforcing steel or forms for the bridge rail or barrier.				
7* <sup>, Δ</sup>	Concrete overlays  Legal Loads; Heavy stationary loads with th Engineer's approval.***					
10 *, \(^{\Delta}\) (15)**, \(^{\Delta}\)	Subdeck, one-course deck or post- tensioned haunched slab bridges	Light truck traffic (gross vehicle weight less than 5 tons).****				
14 *, \(^{\Delta}\) (21)**, \(^{\Delta}\)	Subdeck, one-course deck or post- tensioned haunched slab bridges	Legal Loads; Heavy stationary loads with the Engineer's approval.***Overlays on new decks.				
28	Bridge decks	Overloads, only with the State Bridge Engineer's approval.***				



21

- Superstructures
- Load Limitations during cure period
- Table 710-2
- 3 days placing reinforcing steel and form work
- Maintain wet cure





- Superstructures
- Load Limitations during cure period
- Table 710-2
- 14 days Legal Loads
- Maintain wet cure





23





1

### Keys to being successful

- Relax and remember you can pass this class.
- Ask questions.
- Don't memorize the details/specs, they change too often. <u>Learn how and where to find the details</u>; Standard specifications, plans, special provisions, project specific special provisions.
- Be respectful to others.
- Enjoy yourself.



- · Concrete Slump:
  - The designated slump for a concrete mix design is 3". What is the acceptable slump range?
    - Designate a slump for each concrete mix design that is required for satisfactory placement of the concrete application. Reject concrete with a slump that limits the workability or placement of the concrete.
    - If the designated slump is 3 inches or less, the tolerance is ± ¾ inch, or limited by the
      maximum allowable slump for the individual type of construction.
    - If the designated slump is greater than 3 inches the tolerance is ± 25% of the designated slump.
    - For drilled shafts the target slump just prior to being pumped into the drilled shaft is 9 inches. If the slump is less than 8 inches, redoes the concrete with admixtures as permitted in subsection 401.3i.
    - Do not designated a slump in excess of 5 inches for all other structural concrete.



3

## **Concrete and Reinforcing Steel Review 2**

- · Concrete Slump:
  - The designated slump for a concrete mix design is 3". What is the acceptable slump range?
  - 3" ≤ 3" → Tolerance is ± ¾"
     3" ¾" = 2¼"
    - $3" + \frac{3}{4}" = \frac{3}{4}"$
  - The acceptable range is 21/4" to 33/4"



- Placement Time:
  - If ambient air temp. is 76° F and the agitated concrete temperature at the time of placement is 80° F, what is the maximum time allowed for placement of the concrete after water is added to the mix? No set retarding admixture is added.



5

## **Concrete and Reinforcing Steel Review 4**

- 401.8 Mixing, Delivery and Placement Limitations
- Non-agitated Concrete place within 30 minutes of adding the cement to the water
- Agitated Concrete use Table 401-5

TABLE 401-5: AMBIENT AIR TEMPERATURE AND AGITATED CONCRETE PLACEMENT TIME			
T = Ambient Air Temperature at Time of Batching (°F)	Time limit agitated concrete must be placed within, after the addition of cement to water (hours)	Admixtures	
T < 75	1 1/2	All Cases	
75 ≤ T < 90	1	None	
75 ≤ T < 90	1 1/2	Set Retarder	
ï	ĭ		
Tc= Concrete Temperature at time of placement (°F)	Time limit agitated concrete must be placed within, after the addition of cement to water (hours)	Admixtures	
90 ≤ T <sub>c</sub> *	3/4	All Cases	
Other conditions contributing to quick stiffening of concrete	3/4	All Cases	



- Placement Time:
  - If ambient air temp. is 76° F and the agitated concrete temperature at the time of placement is 80° F, what is the maximum time allowed for placement of the concrete after water is added to the mix? No set retarding admixture is added.
  - The maximum time allowed for placement of the concrete after water is added to the mix is 1 hour (See 401.8.a)



7

## Concrete and Reinforcing Steel Review 6

- Placement Time:
  - If ambient air temp. is 76° F and the agitated concrete temperature at the time of placement is 80° F, what is the maximum time allowed for placement of the concrete after water is added to the mix? <u>A set</u> retarding admixture is added.
  - The maximum time allowed for placement of the concrete after water is added to the mix is 1.5 hours (See 401.8.a)



- Placement Time:
  - What is the maximum time allowed for placement of agitated concrete if the ambient air temp. is 99° F and the concrete temp. at the time of placement is 90° F? No set retarding admixture is added.
  - The maximum time allowed for placement of the concrete after water is added to the mix is 45 minutes (See 401.8.a)
  - If concrete temp. ≥ 90°F, 45 min. placement time



# Falsework & Form Construction Review

F&F-1

1

### **Example Questions:**


Q1: Concrete columns for a single column bent pier were poured yesterday. How long from concrete placement can pier beam formwork erection start?

- 1. Structural Element?

  Single Column Bent
- 2. Type of Work?

  Pier Beam Formwork





### **Example Questions:**


Q2: The <u>concrete deck</u> for a steel girder bridge was placed on October 15th. The width of the deck is 60'. There are 6 girders spaced at 7'-3". No test specimens were made. How many days between the deck placement and when the deck forms can be removed?

- 1. Structural Element?

  Deck, girders spaced at 7.25 Ft.
- 2. Type of Work? removal of Deck Forms



L 4



### **Example Questions**

Q3: The <u>concrete deck</u> for a steel girder bridge was placed on October 15th. The width of the deck is 60'. There are 6 girders spaced at 7'-3". No test specimens were made. <u>Supplemental cementitious materials were added</u>. How many days between the deck placement and when the deck forms can be removed?


1. Structural Element?

Deck, girders spaced at 7.25 Ft with S.C.M.'s

2. Type of Work? removal of Deck Forms



\_




### **Example Questions:**

Q5: Wing Walls for a RFB was placed October 3<sup>rd</sup>. No Supplemental Cementitious materials were added. How many days between the concrete placement and the removal of forms if no test specimens were made?

- 1. Structural Element? Wing Walls
- 2. Type of Work? removal of Wing Wall Forms





**Example Questions:** 

Q6: Same structure as Q5. How many days if grade 4.0 concrete (4000 psi) is specified, and test specimens broke at a strength of 2800 psi after 3 days?

1. Structural Element?

Deck, girders spaced at 11 Ft.

+ Cylinders made, broke on Day 4

Requirement for: + = reduce days if attain 65% of f'c


0.65(4000) = 2600 psi Needed

break of 2800 > 2600 req'd, OK.

Remove forms on Day 3 after breaks.

2. Type of Work? removal of Wing Wall Forms





700 STRUCTURES 701 702 703 TEMPORARY SHORING CONTROLLED DEMOLITION 700-2 DRILLED SHAFTS 700-6 700-15 PILING DESCRIPTION 704.1 700-15 MATERIALS 700-15 PILE DRIVING EQUIPMENT 700-15 General Hammers for Steel Piles, Steel Sheet Piles and Shells for Cast-in-Place Conc. Pile 700-15 Hammers for Pre-Stressed Concrete Pile 700-16 Vibratory Hammers 700-16 Additional Equipment 700-16 Leads 700-16 Hammer Cushion Pile Driving Head 700-16 Water Jets 700-16 CONSTRUCTION REQUIREMENTS Order Lists, Piles and Test Pile 700-17 **Driving Piles** 700-17 700-18 700-19 Bearing Values and Required Penetration Piling Restrike Procedure Pile Cut-Off and Pile Painting 700-20 Cast-In-Place Concrete Piles 700-20 Sheet Pile
MEASUREMENT AND PAYMENT 700-20 700-21 STRUCTURAL STEEL FABRICATION 700-22 706 707 BEARINGS AND PADS FOR STRUCTURES EXPANSION DEVICES 700-33 FALSEWORK AND FORM CONTSTRUCTION STEEL PERMANENT DECK FORMS 700-39

## Say there was a question about the **(finished) smoothness of a bridge deck:** where would one look?

705		STRUCTURAL STEEL FABRICATION					
706		BE	ARINGS AND PADS FOR STRUCTURES				
707		EX	PANSION DEVICES	700-33			
708		FA	LSEWORK AND FORM CONTSTRUCTION	700-35			
709		ST	EEL PERMANENT DECK FORMS	700-39			
710		CONCRETE STRUCTURE CONSTRUCTION					
	710.1		DESCRIPTION	700-40			
	710.2		MATERIALS	700-40			
	710.3		CONSTRUCTION REQUIREMENTS	700-40			
		a.	Falsework and Forms	700-40			
		b.	Handling and Placing Concrete	700-40			
		c.	c. Construction Joints, Expansion Joints and End of Wearing Surface Treatment				
		d. Finishing		700-43			
		e.	Curing and Protection	700-44			
		f.	Grinding and Grooving	700-46			
		g.	Removal of Forms and Falsework	700-47			
		h.	Bridge Number Marking	700-49			
	710.4	MI	ASUREMENT AND PAYMENT	700-49			

13

#### 710 CONCRETE STRUCTURE CONSTRUCTION 710.3 CONSTRUCTION REQUIREMENTS d. Finishing

700-43

d. Finishing. Finish all top surfaces, such as the top of retaining walls, curbs, abutments and rails, with a wooden float by tamping and floating, flushing the mortar to the surface and provide a uniform surface, free from pits or porous places. Trowel the surface producing a smooth surface, and brush lightly with a damp brush to remove the glazed surface.

Strike off bridge decks with a self-propelled finishing machine, which may be manually operated by winches to reach a temporary bulkhead when approved by the Engineer. The screed on the finish machine must be self-oscillating, and operate or finish from a position either on the skew or transverse to the bridge roadway centerline.

On decks skewed greater than 10°, operate the finishing machine on the same skew as the bridge, unless approved otherwise by the SBO. Before placing concrete, position the finisher throughout the proposed placement area allowing the Engineer to verify the reinforcing steel positioning.

Irregular sections may be finished by other methods approved by the Engineer. Reinforced concrete box bridges that will be under fill may be struck off by other approved methods.

Float and straightedge the wearing surface so the finished surface is at the cross-section shown in the Contract Documents. Do not add water to the surface of concrete, unless approved by the Engineer, and when approved apply as a fog spray.

Secure a smooth riding bridge deck, correcting surface variations exceeding 1/2 inch in 10 feet by use of an approved profiling device, or other method approved by the Engineer.

Straightedge decks that are to receive an overlay, leaving them with an acceptable float or machine pan finish.

For decks not receiving an overlay, and without the bid item Bridge Deck Grooving, finish the deck with the rough burlap drag.

For decks not receiving an overlay, and with the bid item Bridge Deck Grooving, see subsection 710.3f. for grooving requirements.



#### 710 CONCRETE STRUCTURE CONSTRUCTION 710.3 CONSTRUCTION REQUIREMENTS d. Finishing

700-43

d. Finishing. Finish all top surfaces, such as the top of retaining walls, curbs, abutments and rails, with a wooden float by tamping and floating, flushing the mortar to the surface and provide a uniform surface, free from pits or porous places. Trowel the surface producing a smooth surface, and brush lightly with a damp brush to remove the glazed surface.

Strike off bridge decks with a self-propelled finishing machine, which may be manually operated by winches to reach a temporary bulkhead when approved by the Engineer. The screed on the finish machine must be self-oscillating, and operate or finish from a position either on the skew or transverse to the bridge roadway

On decks skewed greater than 10°, operate the finishing machine on the same skew as the bridge, unless approved otherwise by the SBO. Before placing concrete, position the finisher throughout the proposed placement area allowing the Engineer to verify the reinforcing steel positioning.

Irregular sections may be finished by other methods approved by the Engineer. Reinforced concrete box bridges that will be under fill may be struck off by other approved methods.

Float and straightedge the wearing surface so the finished surface is at the cross-section shown in the Contract Documents. Do not add water to the surface of concrete, unless approved by the Engineer, and when approved apply as a fog spray.

Secure a smooth riding bridge deck, correcting surface variations exceeding ½ inch in 10 feet by use of an

approved profiling device, or other method approved by the Engineer.

Straightedge decks that are to receive an overlay, leaving them with an acceptable float or machine pan

For decks not receiving an overlay, and without the bid item Bridge Deck Grooving, finish the deck with the rough burlap drag.

For decks not receiving an overlay, and with the bid item Bridge Deck Grooving, see subsection 710.3f. for grooving requirements



15

#### Say there was a question about the form removal for ornamental (structural) rubbed finish work: where would one look?

705		ST	RUCTURAL STEEL FABRICATION	700-22	
706		BE	ARINGS AND PADS FOR STRUCTURES	700-32	
707		EX	PANSION DEVICES	700-33	
708		FA	LISEWORK AND FORM CONTSTRUCTION	700-35	
709		ST	EEL PERMANENT DECK FORMS	700-39	
710		CC	DNCRETE STRUCTURE CONSTRUCTION	700-40	
	710.1		DESCRIPTION	700-40	
	710.2		700-40		
	710.3		CONSTRUCTION REQUIREMENTS	700-40	
		a.	Falsework and Forms	700-40	
		b.	Handling and Placing Concrete	700-40	
		c.	Construction Joints, Expansion Joints and End of Wearing Surface Treatment	700-42	
		d.	Finishing	700-43	
		e.	Curing and Protection	700-44	
		f.	Grinding and Grooving	700-46	
		g.	Removal of Forms and Falsework	700-47	
		h.	Bridge Number Marking	700-49	
	710.4	MI	700-49		

### 710 CONCRETE STRUCTURE CONSTRUCTION 710.3 CONSTRUCTION REQUIREMENTS

g. Removal of Forms and Falsework

700-47

g. Removal of Forms and Falsework. Do not remove forms and falsework without the Engineer's approval. During cold weather, the specified time limits may be increased at the discretion of the Engineer, based upon the amount of protection and curing afforded the concrete.

Do not remove forms and falsework until the minimum amount of time required for strength gain has elapsed regardless if the concrete is fully cured per TABLE 710-1.

If forms are removed before expiration of the cure period, maintain the cure as provided in **DIVISION 700**. Remove forms on handrails, ornamental work and other vertical surfaces that require a rubbed finish as soon as the concrete has hardened sufficiently that it shall not be damaged.

Under normal conditions, the Engineer will allow removal of forms and falsework according to TABLE 710-3. The determination of the time requirement for the removal of forms commences after all the concrete for the placement is in place and finished. If high early strength concrete is used, the specified time limits may be decreased as determined by the Engineer, and agreed upon before placing the concrete.



17

## 710 CONCRETE STRUCTURE CONSTRUCTION 710.3 CONSTRUCTION REQUIREMENTS g. Removal of Forms and Falsework

700-47

g. Removal of Forms and Falsework. Do not remove forms and falsework without the Engineer's approval. During cold weather, the specified time limits may be increased at the discretion of the Engineer, based upon the amount of protection and curing afforded the concrete.

Do not remove forms and falsework until the minimum amount of time required for strength gain has elapsed regardless if the concrete is fully cured per TABLE 710-1.

If forms are removed before expiration of the cure period, maintain the cure as provided in **DIVISION** 700. Remove forms on handrails, ornamental work and other vertical surfaces that require a rubbed finish as soon as the concrete has hardened sufficiently that it shall not be damaged.

Under normal conditions, the Engineer will allow removal of forms and falsework according to TABLE 710-3. The determination of the time requirement for the removal of forms commences after all the concrete for the placement is in place and finished. If high early strength concrete is used, the specified time limits may be decreased as determined by the Engineer, and agreed upon before placing the concrete.



# Say there was a question about minimum production rate for a concrete bridge overlay: where would one look?

717		BR	RIDGE OVERLAYS 70		700-91
	717.1		DE	ESCRIPTION	700-91
	717.2		M	MATERIALS	
	717.3		CC	DNSTRUCTION REQUIREMENTS	700-91
		a.		Equipment	700-91
		b.		Preparation of Surface	700-92
		c.		Placing Concrete	700-92
		d.		Finishing	700-92
		e.		Curing and Protection	700-93
		f.		Weather Limitations	700-93
		g.		Limitations of Operations	700-93
		h.		Construction Joints	700-93
		i.		Sealing Vertical Faces of the Overlay	700-93
		j.		Correction of Unbonded Areas	700-93
	717.4		М	ETHOD OF MEASUREMENT AND BASIS OF PAYMENT	700-93



19

# 717 BRIDGE OVELAYS 717.3 CONSTRUCTION REQUIREMENTS a. Equipment

700-91

#### 717.3 CONSTRUCTION REQUIREMENTS

a. Equipment. Use a finishing machine consisting of a mechanical strike-off capable of providing a uniform thickness of concrete slightly above finish grade in front of an oscillating screed or screeds. The finishing machine will be inspected and approved by the Engineer before work is started on each project.

Use a minimum of 1 oscillating screed capable of consolidating the concrete by vibration to 100% of the vibrated unit weight with the following features:

- Install identical vibrators so a minimum of 1 vibrator is provided for each 5 feet of screed length;
- Bottom face a minimum of 5 inches wide with a turned up or rounded leading edge;
- Effective weight a minimum of 75 pounds for each square foot bottom face area;
- Positive control of vertical position, the angle of tilt and the shape of the crown;
- Design together with appurtenant equipment to obtain positive machine screeding of the plastic
  concrete as close as practical to the face of the existing curb line;
- Length sufficient to uniformly strike-off and consolidate the width of the lane to be paved;
- Forward and reverse motion under positive control;
- Supporting rails which are fully adjustable (not shimmed) to obtain the correct profile, unless
  otherwise approved by the Engineer. Provide supports which are sufficiently rigid and do not deflect
  under the weight of the machine. Anchor the supporting rails to provide horizontal and vertical
  stability; and
- Equip to travel on the completed lane when placing concrete in a lane abutting a previously completed
  lane.

Manufacturer's specifications or certification may be used as verification of the oscillating screed requirements.

A drum roller equipped to perform all functions outlined for the oscillating screed above, may be used for finishing the overlay concrete in lieu of an oscillating screed. Equip the drum roller to vibrate by either a factory or



#### 717 BRIDGE OVELAYS 717.3 CONSTRUCTION REQUIREMENTS a. Equipment

700-92

#### 717 - BRIDGE OVERLAYS

field adaptation. The drum roller must be able to compact the concrete to a minimum of 100% of the consolidated

unit weight.

Provide an overall combination of labor and equipment with the capability for proportioning, mixing, placing and finishing new concrete at the following minimum rates shown in TABLE 717-1.

TABLE 717-1: PORTLAND CEMENT CONCRETE OVERLAY PRODUCTION REQUIREMENTS					
Total Placed Surface Area per Bridge (Square Yards)	Minimum Cubic Yards per Hour				
0-328	1.0				
329-492	1.5				
493-656	2.0				
Over 656	2.5				



# **CIT Structures**

# **Pile Driving Review**






1

## 1. Mathematics Order of Operations

- Be sure to remember the rules of math while calculating pile bearing
- PEMDAS
- Parentheses
- Exponents
- Multiplication
- Division
- Addition
- Subtraction





- P= safe bearing power in pounds
- W= weight in pound, of striking part of hammer
- H= height of fall in feet
- S= the average penetration in inches per blow
- X= weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving



3

#### 3. Pile Driving Review

- Pile Designation
  - •HP 12 X 53
  - •"H" pile
  - •12" in width and depth
  - Weighs 53 lbs. per foot



- Drive distance
  - •S = Average penetration in inches per blow
  - •5 blows for gravity hammer
  - •20 blows for air/steam & diesel



5

#### 5. Pile Driving Review

Diesel Hammer





TABLE 704-1: PILE FORMULAS						
Hammer	Pile Type	Formula				
Gravity	Timber	$P = \frac{2  W  H}{S + 1.0}$				
Gravity	Steel Steel Shell Steel Sheet	$P = \frac{3  W  H}{S + 0.35}  \left(\frac{W}{(W + X)}\right)$				
Air/Steam (Single Acting)	All Types	$P = \frac{2  W  H}{S + 0.1}$				
Air/Steam (Double Acting)	All Types	$P = \frac{2}{S + 0.1}$				
Delmag and McKierman-Terry*	All Types	$P = \frac{1.6 \text{ W H}}{S + 0.1 \left(\frac{X^{**}}{W}\right)}$				
Link-Belt*	All Types	$P = \frac{1.6 \text{ E}}{S + 0.1 \left(\frac{X^{**}}{W}\right)}$				

\*diesel hammers

\*diesel hammers, the quantity X/W shall not be less than 1.

P = safe bearing power in pounds

W = weight in pounds, of striking part of hammer

H = height of fall in feet

E = energy of ram in foot-pounds per blow

S = the average penetration in inches per blow for the last 5 blows for gravity hammers and the last 20 blows for air/steam or diesel hammers

X = weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving



## 7. Pile Driving Review

• Delmag Diesel Hammer Pile Formula

$$P = 1.6 W H$$
  
S+ 0.1 (X/W\*\*)



- Pile Driving Review
  - Pile is a 10 x 42 and 26 feet long
  - Delmag Diesel D19-42 Hammer and the striking part of the hammer weighs 4,190 lbs
  - Cap and Anvil weigh 1,200 lbs
  - Height of fall 10 feet
  - 2.0" total in 20 blows for an average penetration 0.10 inches



9

#### 9. Pile Driving Review

• Delmag Diesel Hammer Pile Formula

$$P = 1.6 * 4190 * 10$$

$$0.10+0.1(2292/4190**)$$

```
( 10 = FALL )
( S = 2.0/20 )
( X= 1200+(42 X 26) )
```



• Delmag Diesel Hammer Pile Formula

$$P = \frac{67040}{0.10+0.1(0.55^{**})}$$

\*\* Diesel quantity x/w shall not be < 1



11

#### 11. Pile Driving Review

• Delmag Diesel Hammer Pile Formula

$$P = \frac{67040}{0.10+0.1(1.00**)}$$

\*\* Diesel quantity x/w shall not be < 1



• Delmag Diesel Hammer Pile Formula



13

# 13. Pile Driving Review

• Delmag Diesel Hammer Pile Formula



• Delmag Diesel Hammer Pile Formula

P = 335200 lbs / 2000

P = 168 tons



15

# 15. Pile Driving Review

- Air/Steam Hammer
- Single Action



T	ABLE 704-1: PILE	FORMULAS	
Hammer	Pile Type	Formula	
Gravity	Timber	$P = \frac{2  W  H}{S + 1.0}$	
Gravity	Steel Steel Shell	$P = \frac{3 \text{ W H}}{S + 0.33} \left( \frac{\text{W}}{(W + \text{Y})} \right)$	
	Steel Sheet	510.55 ((11.5))	
Air/Steam (Single Acting)	All Types	$P = \frac{2  W  H}{S + 0.1}$	
Air/Steam	A 11 T	2 F	
(Double Acting)	All Types	S+0.1	
Delmag and McKierman-Terry*	All Types	$P = \frac{1.6  W  H}{S + 0.1  \left(\frac{X^{**}}{W}\right)}$	
Link-Belt*	All Types	$P = \frac{1.6 \text{ E}}{S + 0.1 \left(\frac{X^{**}}{W}\right)}$	

\*\*diesel hammers

\*\* For diesel hammers, the quantity X/W shall not be less than 1.

P = safe bearing power in pounds

W = weight in pounds, of striking part of hammer

H = height of fall in feet

E = energy of ram in foot-pounds per blow

S = the average penetration in inches per blow for the last 5 blows for gravity hammers and the last 20 blows for air/steam or diesel hammers

X = weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving



17

# 17. Pile Driving Review

• Conmaco Air/Steam Hammer

$$P = \frac{2 \text{ W H}}{S + 0.1}$$



- Pile Driving Review
  - Pile is a 14 x 89 and 20 feet long
  - Conmaco E65 Air/Steam Hammer and the striking part of the hammer weighs 6,500 lbs
  - (For Air/Steam Hammer the weight of Pile, Cap and Anvil are not used in the calculations)
  - Height of fall 5 feet
  - 1.0" total in 20 blows for an average penetration 0.05 inches



19

#### 19. Pile Driving Review

• Conmaco Air/Steam Hammer

$$P = \frac{2 + 6500 + 5}{0.05 + 0.1}$$

$$(5 = fall)$$
  
 $(S = 1.0/20)$ 



• Conmaco Air/Steam Hammer

$$P = 65000$$
 $0.05 + 0.1$ 



21

# 21. Pile Driving Review

• Conmaco Air/Steam Hammer



• Conmaco Air/Steam Hammer

P = 433333 lbs / 2000

P = 217 tons



23

# 23. Pile Driving Review

- Gravity Hammer
- Steel H-Pile



TABLE 704-1: PILE FORMULAS					
Hammer	Pile Type	Formula			
Gravity	Timber	$P = \frac{2  W  H}{S + 1.0}$			
Gravity	Steel Steel Shell Steel Sheet	$P = \frac{3  W  H}{S + 0.35}  \left(\frac{W}{(W + X)}\right)$			
Air/Steam (Single Acting)	All Types	$P = \frac{2  W  H}{S + 0.1}$			
Air/Steam (Double Acting)	All Types	$P = \frac{2 - E}{S + 0.1}$			
Delmag and McKierman-Terry*	All Types	$P = \frac{1.6  W  H}{S + 0.1  \left(\frac{X^{**}}{W}\right)}$			
Link-Belt*	All Types	$P = \frac{1.6 \text{ E}}{S + 0.1 \left(\frac{X^{**}}{W}\right)}$			

\*diesel hammers

\*\* For diesel hammers, the quantity X/W shall not be less than 1.

P = safe bearing power in pounds

W = weight in pounds, of striking part of hammer

H = height of fall in feet

E = energy of ram in foot-pounds per blow

S = the average penetration in inches per blow for the last 5 blows for gravity hammers and the last 20 blows for air/steam or diesel hammers

X = weight in pounds of the pile plus the weight of any cap and/or anvil used on the pile during driving



25

## 25. Pile Driving Review

$$P = \frac{3 W H}{S+(0.35)} \left( \frac{W}{W+X} \right)$$



- Pile Driving Review
  - Pile is a 12 x 53 and 15 feet long
  - Gravity Hammer and the striking part of the hammer weighs 4,050 lbs
  - Cap and Anvil weighs 900 lbs
  - Height of fall 8 feet
  - 1.0" total in 5 blows for an average penetration 0.2 inches



27

#### 27. Pile Driving Review

$$P = \underbrace{\frac{3 \ 4050 \ 8}{0.2 + (0.35)}}_{(4050 + 1695)} \underbrace{\frac{4050}{4050 + 1695}}_{(4050 + 1695)}$$



• Gravity Hammer w/ Steel H Pile

$$P = \frac{3 \ 4050 \ 8}{0.55} \left[ \frac{4050}{5745} \right]$$



29

## 29. Pile Driving Review

$$P = \begin{array}{c} 97200 \\ \hline 0.55 \end{array} \left( \begin{array}{c} 4050 \\ 5745 \end{array} \right)$$



• Gravity Hammer w/ Steel H Pile



31

## 31. Pile Driving Review

$$P = 62 \text{ tons}$$



